

**SURVEY &  
REMONUMENTATION**

SEP 08 1998

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in SECTION

Gogebic  
(County)

Located In: Corner Code ##

- |                                    |   |            |   |            |       |
|------------------------------------|---|------------|---|------------|-------|
| 1. Public Land Survey              | T | <u>48N</u> | R | <u>45W</u> | A-12  |
|                                    | T | _____      | R | _____      | _____ |
|                                    | T | _____      | R | _____      | _____ |
|                                    | T | <u>48N</u> | R | <u>46W</u> | M-12  |
| 2. Property Controlling in Section | S | _____      | T | _____      | _____ |
|                                    | S | _____      | T | _____      | _____ |
| 3. Miscellaneous Property in Sec.  | S | _____      | T | _____      | _____ |
|                                    | S | _____      | T | _____      | _____ |

Register's Office }  
Gogebic County } ss.

Received for record the  
18<sup>th</sup> day of JUNE  
A. D. 1998 at 1:30 o'clock  
P m., and recorded in  
Liber 7 of CORNERS  
on page 8  
Samuel Collins Dep  
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

$\frac{1}{4}$  Corner 31 & 36; T.48 N., R.45-46 W.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Richard L. Drahn, in a field survey on June 15, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by John Burt on 9/10/1847. Original B.T.s --- Hemlock 6" S.15 E. 14 links (9.24') --- Sugar 4" N.19 W. 13 links (8.58') --- Corner restored by Richard L. Drahn (21564) on 5/22/84 from the remains of the original Hemlock B.T., a line tree north and distance north to a recovered section corner. He set a 2" X 30" aluminum pipe with a 3 $\frac{1}{4}$ " stamped aluminum cap and the following new bearing trees:

- |     |                 |         |        |
|-----|-----------------|---------|--------|
| 13" | Basswood        | N.35 W. | 35.09' |
| 5"  | Sugar Maple     | N.50 E. | 28.69' |
| 14" | Sugar Maple     | S.43 E. | 41.79' |
| 6'  | Steel sign rail | N.54 W. | 1.9'   |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner recorded in Gogebic County in Liber 2, Page 661 on 12/10/84.

Corner research on file with Gogebic County records.

Recovered the monument as described and the bearing trees as follows:

- |     |                 |         |        |
|-----|-----------------|---------|--------|
| 15" | Basswood        | N.34 W. | 35.09' |
| 6"  | Sugar Maple     | N.50 E. | 28.67' |
| 16" | Sugar Maple     | S.41 E. | 41.77' |
| 6'  | Steel sign rail | N.55 W. | 1.81'  |

A stump hole with Hemlock bark is all that remains of the original B.T.s

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing tree referenced:

- |     |             |         |        |
|-----|-------------|---------|--------|
| 18" | Sugar Maple | S.02 W. | 13.02' |
|-----|-------------|---------|--------|

**PEER GROUP APPROVED**

Richard L. Drahn 6/17/98  
COUNTY REGISTER



Signed by Richard L. Drahn Date June 17, 1998

Surveyor's Michigan License No. 21564