

**SURVEY &
REMONUMENTATION**

SEP 08 1998

SECTION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Gogebic</u> <small>(County)</small>		Located In:	Corner Code #
1. Public Land Survey	T <u>48N</u> R <u>45W</u>		<u>B-7</u>
	T _____ R _____		_____
	T _____ R _____		_____
	T _____ R _____		_____
2. Property Controlling in Section	S _____ T _____ R _____		_____
	S _____ T _____ R _____		_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____		_____
	S _____ T _____ R _____		_____

Register's Office
Gogebic County

Received for record the
23RD day of JULY
A. D. 1998 at 11:40 o'clock
A m., and recorded in
Liber 7 of CORNERS
on page 34
Ramona Collins Deputy
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

$\frac{1}{4}$ Corner 18 & 19; T.48 N., R.45 W.

(Richard L. Drahn in a field survey on July 8, _____, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7	●												
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on 9/29/1848. Original B.T.s --- Hemlock 16" N.63 W. 27 links (17.82') --- Y. Birch 10" S.72 E. 17 links (11.22') ---

C. Supercynski, on 5/15/35 recovered the Hemlock still scribed.

Corner restored by Richard L. Drahn (21564) on 8/15/84 from the remains of the two original B.T.s, Supercynskis' tag tree and a line tree east. He set a 2" X 30" aluminum pipe with a 3 $\frac{1}{4}$ " stamped aluminum cap and the following:

5"	Red Maple	N.22 W.	28.72'
6"	Black Ash	S.87 E.	7.53'
14"	Black Ash	S.34 W.	29.12'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

6'	Steel sign rail	S.04 W.	2.79'
----	-----------------	---------	-------

Corner recorded in Gogebic County Liber 2, Page 663 on 12/10/84.

Corner research on file with Gogebic County records.

Recovered the monument as described and the bearing trees as follows:

6"	Red Maple	N.22 W.	28.67'
6"	Black Ash	S.89 E.	7.52'
14"	Dead Black Ash	S.34 W.	dead and down
6'	Steel sign rail	S.06 W.	2.81'

A badly decayed hemlock stump and a stump hole are all that remain of the original bearing trees.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing trees established

7"	Red Maple	N.73 E.	18.61'
7"	Red Maple	S.37 W.	23.34'

Resource grade GPS Lat 46-32-58.11 N
Long 89-58-48.54 W

PEER GROUP APPROVAL

Richard L. Drahn 7/22/98
COUNTY REGISTER



Signed by Richard L. Drahn Date July 19, 1998

Surveyor's Michigan License No. 21564