

**SURVEY &
REMONUMENTATION**

SEP 08 1998

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

Register's Office }
Gogebic County } ss.

Received for record the
18TH day of JUNE
A. D. 1998 at 1:30 o'clock
P m., and recorded in
Liber 7 of CORNERS
on page 9
Ramona L. Collins, Dep
Register of Deeds

For corners in SECTION

| | | |
|---------------------------------------|----------------------------|---------------|
| <u>Gogebic</u> (County) | Located In: | Corner Code # |
| 1. Public Land Survey | T <u>48N</u> R <u>45</u> W | <u>B-9</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

$\frac{1}{4}$ Corner 19 & 30; T.48 N., R.45 W.

I, Richard L. Drahn in a field survey on June 16, 1998, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

| | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| A | B | C | D | E | F | G | H | I | J | K | L | N |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on 9/27/1848. Original B.T.s --- Sugar 8" S.70 E. 11 links (7.26') --- Sugar 20" N.33 W. 17 links (11.22') ---
Corner restored by Richard L. Drahn (21564) from the stump holes of the two original B.T.s, natural feature ties west, a line tree east and distance east and west to recovered corners. He set a 2" X 36" iron pipe with a 3" stamped brass cap and the following new B.T.s:

| | | | |
|-----|--------------|---------|--------|
| 8" | Sugar Maple | N.68 W. | 27.90' |
| 8" | Yellow Birch | N.26 E. | 41.00' |
| 15" | Sugar Maple | S.57 E. | 31.55' |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

6' Steel sign rail N.36 W. 2.05'

Corner recorded in Gogebic County in Liber 2, Page 665 on 12/10/84.

Corner research on file with Gogebic County records.

Recovered the monument as described and the bearing trees as follows:

| | | | | |
|-----|-----------------|---------|--------|------------|
| 9" | Sugar Maple | N.66 W. | 27.87' | (new nail) |
| 10" | Yellow Birch | N.25 E. | 41.02' | " " |
| 17" | Sugar Maple | S.60 E. | 31.55' | " " |
| 6' | Steel sign rail | N.37 W. | 2.02' | |

Stump holes are all that remains of the original B.T.s.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing tree referenced:

4" Sugar Maple S.31 W. 36.28'

PEER GROUP APPROVED
Richard L. Drahn 6/17/98
COUNTY REPRESENTATIVE



Signed by Richard L. Drahn Date June 16, 1998

Surveyor's Michigan License No. 21564