

**SURVEY &  
REMONUMENTATION**

SEP 08 1998

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

**SECTION**

Register's Office }  
Gogebic County } ss.

Received for record the  
18<sup>TH</sup> day of JUNE  
A. D. 1998 at 1:30 o'clock  
P m., and recorded in  
Liber 7 of CORNERS

on page 10.  
Ramona L. Collins, Dep.  
Register of Deeds

Register of Deeds Stamp & File Number

<u>Gogebic</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>48N</u> R <u>45W</u>	<u>B-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

$\frac{1}{4}$  Corner 30 & 31; T.48 N., R.45 W.

I, Richard L. Drahn in a field survey on June 15, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11	●												
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on 9/27/1848. Original B.T.s --- Hemlock 14" S.45 W. 33 links (21.78') --- Hemlock 10" N.40 E. 24 links (15.84') --- R.G. Campbell on 5/10/35 recovered the NE B.T. still scribed. Corner restored by Richard L. Drahn on 5/10/84 from the remains of the two original B.T.s. He set a 3/4" X 48" solid aluminum rod with a 3/4" stamped aluminum cap and the following new bearing trees:

8"	Basswood	N.10 W.	17.58'
10"	Sugar Maple	S.21 E.	21.59'
15"	Hemlock	S.59 W.	60.38'
6'	Steel sign rail	N.06 E.	2.2'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner recorded in Gogebic County in Liber 2, Page 667 on 12/10/84.

Corner research on file with Gogebic County records.

Recovered the monument as described and the bearing trees as follows:

11"	Dead Basswood	N.10 W.	17.60'
13"	Sugar Maple	S.20 E.	21.54'
18"	Hemlock	S.61 W.	60.31' (new nail)
6'	Steel sign rail	N.05 W.	1.98'

The original B.T.s are both now very badly decayed Hemlock stumps.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing tree referenced:

5"	Sugar Maple	N.15 E.	11.07'
----	-------------	---------	--------

**PEER GROUP APPROVED**  
Richard L. Drahn 6/17/98  
**COUNTY REGISTER**



Signed by Richard L. Drahn Date June 17, 1998

Surveyor's Michigan License No. 21564