

JAN 05 2001

SECTION LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
 Gogebic County } ss.

For corners in

Received for record the
2ND day of OCTOBER
 A. D. 2000 at 10:50 o'clock
A m., and recorded in
 Liber 8 of CORNER
 on page 27.
Ronana Collins Deputy
 Register of Deeds

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	<u>T48 N R45 W.</u>	<u>C-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Section Corner 7, 8, 17 & 18; T.48 N., R.45 W.

I, Richard L. Drahn, in a field survey on Sept. 24, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt on 9/24/184851. Original bearing trees:
 Sugar 16" S.35° W. 14 links (9.24')
 Sugar 8" N.88° E. 10 links (6.60')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I restored the corner position at record bearing and distance from the remains of the two original bearing trees. Both are now a large series of root holes with very badly decayed Sugar Maple wood. The ½ mile distances west and south and the 1 mile distances north and east from corner to monumented corners are in accord with the field notes of the original Government Survey.

A 5" squared Cedar post bears S.14° E., 25.5 feet from the original corner position.

Corner research on file with Gogebic County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 2" X 30" aluminum pipe with a 3 ¼" stamped aluminum cap and the following new blazed and scribed bearing trees: (Measurements taken to a 10p nail in the side of the tree)

Sugar Maple	8"	S.57° E.	27.51'
Red Maple	9"	N.21° E.	8.19'
Sugar Maple	5"	N.61° W.	4.51'
Steel sign rail	6'	S.17° E.	2.08'

Richard L. Drahn
 Richard L. Drahn 9/27/00
 COUNTY REGISTER



Signed by Richard L. Drahn Date September 27, 2000

Surveyor's Michigan License No. 21564 FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1976