

SURVEY & REMONUMENTATION

SEP 08 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office } ss.
Gogebic County }

For corners in

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>48N</u> R <u>45W</u>	<u>C-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Received for record the
23RD day of JULY
A. D. 1998 at 11:40 o'clock
A m., and recorded in
Liber 7 of CORNERS
on page 35
Ramona Collins DePute
Register of Deeds
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Section Corner 17, 18, 19 & 20; T.48 N., R.45 W.

Richard L. Drahn, in a field survey on July 8, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
Corner established by Austin Burt on 9/27/1848. Original B.T.s --- Maple 14" S.55 W. 20 links (13.20') --- Maple 12" N.70 E. 10 links (6.60') ---
Corner position restored by Richard L. Drahn (21564) on 8/15/84 from the remains of the two original B.T.s, and natural features and line trees north, south, east and west. He set a 2" X 30" alum. pipe with a 3 1/2" stamped aluminum cap and the following new B.T.s:
10" Red Maple N.41 E. 20.50'
5" Sugar Maple S.14 E. 18.86'
10" Yellow Birch S.72 W. 31.01'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
6' Steel sign rail S.46 W. 2.39'

Corner recorded in Gogebic County Liber 2, Page 669 on 12/10/84.

Corner research on file with Gogebic County records.

Recovered the monument as described and the bearing trees as follows:

12"	Red Maple	N.40 E.	20.48'
6"	Sugar Maple	S.14 E.	18.84'
11"	Yellow Birch	S.72 W.	31.02'
6'	Steel sign rail	S.47 W.	2.34'

PEER GROUP APPROVED
Richard L. Drahn 7/22/98
COUNTY REGISTER

Shallow stump holes are all that remain of the original B.T.s.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New Bearing tree referenced:
6" Sugar Maple S.40 W. 12.26'

Resource grade GPS Lat 46-32-57.97N
Long 89-58-10.82W



Signed by Richard L. Drahn Date July 19, 1998

Surveyor's Michigan License No. 21564