

SURVEY &  
REMONUMENTATION

SEP 08 1998

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in SECTION  
Gogebic (County)

Located In: Corner Code #  
1. Public Land Survey T 48N R 45W C-9  
T R  
T R  
T R  
2. Property Controlling S T R  
in Section S T R  
3. Miscellaneous S T R  
Property in Sec. S T R

Register's Office }  
Gogebic County } ss.

Received for record the  
18<sup>th</sup> day of JUNE  
A. D. 1998 at 1:30 o'clock  
P. M., and recorded in  
Liber 7 of CORNERS  
page 11  
Ramona L. Collins, Dep  
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Section Corner 19, 20, 29 & 30; T.48 N., R.45 W.

(Richard L. Drahn in a field survey on June 16, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on 9/27/1848. Original B.T.s --- Sugar 10" S.52 W. 20 links (13.20') --- Y. Birch 20" N.67 E.38 links (25.08') ---

Corner restored by Richard L. Drahn (21564) on 6/19/84 from the remains of the original Sugar B.T. and by retracement measurements north, south, east and west to recovered line trees, natural features and recovered corners. He set a 2" X 4' iron pipe with a stamped brass cap and the following B.T.s:

7"	Sugar Maple	N.50 W.	28.20'
22"	Sugar Maple	N.47 E.	57.34'
25"	Sugar Maple	S.12 W.	32.79'
6'	Steel sign rail	S.87 W.	1.3'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner recorded in Gogebic County in Liber 2, Page 673 on 12/10/84.

Corner research on file with Gogebic County records.

Recovered the monument as described and the bearing trees as follows:

8"	Sugar Maple	N.50 W.	28.21'
23"	Sugar Maple	N.47 E.	57.07' (new nail)
26"	Sugar Maple	S.10 W.	32.77'
6'	Steel sign rail	S.88 W.	1.29'

A stump hole is all that remains of the S.52 W. original B.T.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing tree referenced:

6"	Sugar Maple	S.75 W.	14.38'
----	-------------	---------	--------

PEER GROUP APPROVED  
Richard L. Drahn 6/17/98  
COUNTY REGISTER



Signed by Richard L. Drahn Date June 16, 1998

Surveyor's Michigan License No. 21564