

**SURVEY &
REMONUMENTATION**

SEP 08 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

Received for record the
18TH day of JUNE
A. D. 1998 at 1:30 o'clock
1 m., and recorded in
Liber 7 of CORNERS
on page 12
Norman L. Collins, Dep.
Register of Deeds

Register of Deeds Stamp & File Number

For corners in SECTION

Gogebic <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>48N</u> R <u>45W</u>	<u>C-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

$\frac{1}{4}$ Corner 29 & 30; T.48 N., R.45 W.

Richard L. Drahn, in a field survey on June 16, 1998, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on 9/27/1848. Original B.T.s --- Hemlock 10" S.19 $\frac{1}{2}$ " W. 5 links (3.30') --- Sugar 14" N.19 E. 2 links (1.32') --- Corner restored by Richard L. Drahn (21564) on 6/19/84 from the remains of the two original B.T.s, a line tree north and the distances north and south to recovered corners. He set a 2" X 4" iron pipe with a 3" stamped brass cap and the following new bearing trees:

7"	Sugar Maple	N.24 W.	21.77'
10"	Sugar Maple	S.54 E.	9.97'
12"	Sugar Maple	S.36 W.	15.01'
6"	Steel sign rail	N.86 W.	2.0'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner recorded in Gogebic County in Liber 2, Page 675 on 12/10/84.

Corner research on file with Gogebic County records.

Recovered the monument as described and the B.T.s as follows:

9"	Sugar Maple	N.21 W.	21.71'	(new nail)
11"	Sugar Maple	S.56 E.	9.89'	" "
13"	Sugar Maple	S.38 W.	14.99'	" "
6'	Steel sign rail	N.83 W.	1.96'	

A depression from the Hemlock is all that remains of the original B.T.s.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing tree referenced:

9"	Sugar Maple	N.49 E.	11.28'
----	-------------	---------	--------

DEED GROUP APPROVED
Richard L. Drahn 6/17/98
COUNTY REPERMUTATION



Signed by Richard L. Drahn Date June 16, 1998

Surveyor's Michigan License No. 21564