

SURVEY & MONUMENTATION

JAN 05 2001

SECTION

For corners in

Gogebic
(County)

Located In: Corner Code #

1. Public Land Survey

T48N R 45W D-1
T R
T R

2. Property Controlling in Section

S T R
S T R

3. Miscellaneous Property in Sec.

S T R
S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

1/4 Corner 5 & 32; T.48-49 N., R.45 W.

I, Richard L. Drahn in a field survey on Aug. 16, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt on 9/9/1847. Original B.T.s:

Y. Birch	10"	N.35 E.	13 links	(8.58')
Y. Birch	10"	N.55 W.	17 links	(11.22')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I restored the corner position at record bearing and distance from the remains of the two original bearing trees. The first is a series of root holes with Yellow Birch Bark and identifiable wood. The second one is now a series of root holes half buried by logging road construction debris with fragments of Yellow Birch bark. The 40.00 chain distance east and west to recovered corners is in accord with the field notes of the original Government survey. A 9" Red Maple blazed and painted for the corner bears S.12 W. 10.8 feet.

Corner research on file with Gogebic County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 3/4" X 4" solid aluminum marsh rod with stamped aluminum cap and the following new bearing trees:

Yellow Birch	6"	N.24 E.	21.27'
Black Ash	8"	S.62 E.	36.35'
Sugar Maple	12"	N.74 W.	18.36'
Steel sign rail	6'	N.75 E.	1.56'



PEER GROUP APPROVED
Richard L. Drahn 8/23/00
COUNTY REGISTERED SURVEYOR

Signed by Richard L. Drahn
Surveyor's Michigan License No. 21564

Date August 17, 2000

Register of Deeds Stamp & File Number

Register's Office }
Gogebic County } ss.

Received for record the
25th day of AUGUST
A. D. 2000 at 1:20 o'clock
P. m., and recorded in
Book LIBER 8 of CORNERS
Page 20
Kenneth Collins Deputy
Register of Deeds

A	B	C	D	E	F	G	H	I	J	K	L	M
1			●									
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13			●									