

DEC 15 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office } ss.  
Gogebic County }

For corners in

Gogebic  
(County)

Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

1. Public Land Survey	T <u>48N</u> R <u>45W</u>	<u>F-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Received for record the  
17<sup>TH</sup> day of SEPTEMBER  
A. D. 1998 at 1:15 o'clock  
P m., and recorded in  
Liber 47 of CORNERS  
on page 59.

Ramona Collins Deputy  
Register of Deeds

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

$\frac{1}{4}$  Corner 21 & 28; T.48 N., R.45 W.

I, Richard L. Drahn in a field survey on August 21, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on 9/25/1848. Original B.T.s --- Sugar 8" S.10 W. 10 links (6.60') --- Sugar 8" N.03 E. 14 links (9.24') ---

C. Supercynski on 4/17/35 recovered a scribed B.T. at this location.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Restored corner at record bearing and distance from the remains of the two original B.T.s. The first is a badly decayed 16-20" Sugar Maple stump. The second one is now a large stump hole with fragments of decayed Sugar Maple wood.

Corner research on file with Gogebic County records.

**DEED GROUP APPROVAL**  
Richard L. Drahn 9/18/98  
COUNTY REGISTER

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 2" X 30" aluminum monument with a 3 1/2" stamped aluminum cap and the following new B.T.s:

9"	Sugar Maple	N.18 W.	21.79'
8"	Sugar Maple	S.83 E.	21.40'
6"	Sugar Maple	S.31 W.	9.42'
6'	Steel sign rail	N.41 E.	1.91'



Signed by Richard L. Drahn Date August 28, 1998  
Surveyor's Michigan License No. 21564