

DEC 15 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office } ss.
Gogebic County }

SECTION

For corners in

<u>Gogebic</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>48N</u> R <u>45W</u>	<u>G-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Received for record the
17TH day of SEPTEMBER
A. D. 1998 at 1:15 o'clock
P m., and recorded in
Liber 7 of CORNERS
on page 60
Ramona Collins Deputy
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

1/4 Corner 27 & 28; T.48 N., R.45 W.

I, Richard L. Drahn in a field survey on August 27, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on 9/22/1848. Original B.T.s --- 14" Y. Birch S.25 1/2 W. 17 links (11.22') --- 16" Hemlock N.18 E. 21 links (13.86')

Road plans of County Road #519, approved Feb. 1946, indicate this corner as being 45' (scaled) west of station 158 + 80.7 and an 18" culvert as being at station 157 + 75. Local reports by residents indicate that the road has undergone major reconstruction since 1946.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner position found marked by a 1 1/2" iron pipe at the intersection of very old fence lines south and west. Pipe lays 42.2 feet west of station 158 + 80.7. The culvert at station 157 + 75 appears to have been reset since 1946, to station 157 + 71.7, a distance south of 3.3 feet.

All original B.T.s have been destroyed by road construction. Due to the long local usage and its' conformity to the original notes, I have accepted its' location as being the same as established by Austin Burt in 1848.

Corner research on file with Gogebic County records.

BEER GROUP
Richard L. Drahn 9/16/98
COUNTY REGISTER

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 2" X 30" aluminum pipe with a 3 1/4" stamped aluminum cap and the following new B.T.s:

10"	White Pine	S.56 W.	15.86'
9"	Aspen	N.12 E.	4.83'
5"	Balsam	S.26 E.	13.41'
6'	Steel sign rail	S.77 W.	2.10'



Signed by Richard L. Drahn Date August 29, 1998

Surveyor's Michigan License No. 21564