

SEP 08 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

For corners in
Gogebic

Received for record the
14th day of MAY
A. D. 1998 at 3:30 o'clock
P m., and recorded in
Liber 6 of CORNERS
on page 391
Ramona Collins, Dep.
Register of Deeds

| | Located In: | | Corner Code # |
|------------------------------------|--------------|--------------|---------------|
| | Section | Range | |
| 1. Public Land Survey | 34 | 48N 45W | H-13 |
| | T | R | |
| | T | R | |
| | T <u>49N</u> | R <u>45W</u> | <u>H-1</u> |
| | T | R | |
| 2. Property Controlling in Section | S | T | R |
| | S | T | R |
| 3. Miscellaneous Property in Sec. | S | T | R |
| | S | T | R |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

1/4 corner sections 34, T48N, R45W & 3, T47N, R45W

I, John R. Garske, in a field survey on December 11, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|---|----|---|----|---|----|---|----|---|----|---|----|---|
| 1 | | | | | | | | | | | | | |
| 2 | | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | | |
| 4 | | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | | |
| 6 | | 16 | | 17 | | 18 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | | |
| 8 | | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | | |
| 10 | | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | | |
| 12 | | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

Original Township survey by Austin Burt, D.S. in 1847
He set a wood post from which:
Fir 16" N80°E 14 links
Fir 12" N79°W 27 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


No original evidence exists. I established the corner at the centerline intersection of Johnson Road and a two track trail to the east and a fence line/tree line from the west. Distance to existing fences at "40" lines check well with this location and is the most logical position for the 1/4 corner.

(Research on file)

PEER GROUP APPROVED
Richard E. Nelson 5/13/98
COUNTY REGISTER

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I set a 5/8" x 10" long iron rod with a 3 1/4" dia. Bras Cap stamped to identify the corner from which:
Reference Monument (R.M.) - Due West - 33.00 feet, steel sign rail - 1.50 feet
(R.M. - 2 1/3" x 30" long alum. pipe with 3 1/4 diam. alum cap)
Power pole N13°W 127.44 feet
Power Pole S57°W 41.11 feet
7" S. maple N69°E 52.85 feet
NW cor. of Kahila's Garage S45°E 46.16 feet
HSE #361



Signed by John R. Garske
Surveyor's Michigan License No. 28410

Date 5/12/98