

MAR 02 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

For corners in

Gogebic Located In: Corner Code #
(County)

1. Public Land Survey T 48N R 45W I-1
 T R
 T R
 T 49N R 45W I-13
 S T R
 S T R
 3. Miscellaneous S T R
 Property in Sec. S T R

Received for record the
26TH day of AUGUST
 A. D. 1999 at 1:40 o'clock
9 m., and recorded in
 Liber 7 of CORNERS
 on page 232
Rosanna Collins Deputy
 Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Section Corner 2, 3, 34 & 35; T.48-49 N., R.45 W.

I, Richard L. Drahn, in a field survey on July 22, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3					2	1		
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt on 9/9/1847. Original bearing trees:

Cedar	12'	N.64° E.	42 links	(27.72')
Hemlock	12"	N.31° W.	18 links	(11.88')

Corner restored by Neal Spherhake, RLS 7876, on 11/9/61 at the site of an old wood post referenced in 1935 records from the USFS and on line with an original, scribed Maple Witness Tree. He set a 1" X 36" iron pipe with a 4" stamped aluminum cap and the following new bearing trees:

Maple	5'	S.70° E.	40 links	(26.40')
Balsam	8"	S.62° W.	46 1/2 links	(30.69')
Spruce	6"	N.50° W.	44 links	(29.04')
Yellow Birch	12"	N.14° E.	40 links	(26.40')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered Spherhake's monument as described and his bearing trees as follows:

Red Maple	9"	S.70° E.	26.32'	new nail
Balsam dead and down		S.59° W.		
White Spruce	10"	N.50° W.	29.08'	new nail
Yellow Birch	15"	N.16° E.	26.37'	new nail

The Sugar Maple Witness Tree recovered scribed in 1935 and 1961 is now a live, 27" Sugar Maple with the scribing completely grown over bearing S.09°W. 6.93' from the original corner location. No evidence remains of the original bearing trees.

Corner research on file with Gogebic County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing object referenced:

Steel sign rail 6' N.10° E. 2.43'

PEER GROUP APPROVED

Richard L. Drahn 8/24/99
 COUNTY REGISTER



Signed by Richard L. Drahn Date August 10, 1999

Surveyor's Michigan License No. 21564

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, 1971

REVISED MAY 14, 1976

REVISED JAN., 1983

REVISED OCT., 1995

USFS A-17