

Register's Office }  
Gogebic County } ss.

Received for record the

2nd day of OCTOBER  
A. D. 1900 at 10:50 o'clock  
A m., and recorded in  
Book 8 of CORNERS  
at page 32  
Ramona Collins, Deputy  
Register of Deeds

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Gogebic Located In: T48 N R45 W. Corner Code # I-8  
(County)  
1. Public Land Survey T      R       
T      R      SURVEY &  
T      R      MONUMENTATION  
2. Property Controlling S      T      R       
in Section S      T      R       
3. Miscellaneous S      T      R      JAN 05 2001  
Property in Sec. S      T      R       
SECTION

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

¼ Corner 22 & 23; T.48 N., R.45 W.

I, Richard L. Drahn, in a field survey on August 24, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
Original corner established by Austin Burt on 9/20/1851. Original bearing trees:

Maple	8"	S.86 E.	30 links	(19.80')
Maple	8"	N.35 W.	12 links	( 7.92')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I restored the corner position at record bearing and distance from the remains of the two original bearing trees. The first is a large windthrown stump. The second one is now a large Red Maple stump, decayed to well below ground line. Three Red Maple sprouts from 8' to 12" surround the parent tree.

A 19" Red Maple, blazed for the corner bears S.09 W., 22.5 ft. from the original corner location.

Corner research on file with Gogebic County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 30" long aluminum pipe with a 3 ¼" stamped aluminum cap and the following new blazed and scribed bearing trees: (distances taken to a 10p nail in the side of the tree)

Red Maple	12"	N.35 W.	6.66'
Hemlock	12"	S.39 W.	36.96'
Red Maple	12"	N.80 E.	24.08'
Steel sign rail	6'	S.29 E.	2.19'

WEEK GROUP APPROVED  
Richard L. Drahn 9/27/00  
COURT RECORDED

Signed by Richard L. Drahn Date September 23, 2000

Surveyor's Michigan License No. 21564

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971

