

Register's Office  
Gogebic County } ss.

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Received for record the  
2<sup>ND</sup> day of OCTOBER  
A. D. 2000 at 10:50 o'clock  
A m., and recorded in  
Liber 8 of CORNERS  
page 33  
Ramon Collins, Deputy  
Register of Deeds

For corners in

Gogebic Located In: Corner Code #  
(County)

1. Public Land Survey T48 N R45 W. 1-9  
T R  
T R  
T R SURVEY &  
2. Property Controlling S T R MONUMENTATION  
in Section S T R  
3. Miscellaneous S T R  
Property in Sec. S T R JAN 05 2001

Register of Deeds Stamp & File  
Number

SECTION

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Section Corner 22, 23, 26 & 27; T.48 N., R.45 W.

I, Richard L. Drahn, in a field survey on Sept. 25, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt on 9/20/1848. Original bearing trees:  
Cedar 12" S.78° W. 14 links (9.24')  
Y. Birch 12" N.34° E. 35 links (23.10')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I restored the corner position at record bearing and distance from the stump holes of the two original bearing trees. Distances ½ mile north, east and west and 1 mile south to monumented corners is consistent with the field notes of the original Government survey.

A location poster dated 6/6/68 on the north side of a 4" Sugar Maple bears S.06° W., 48.9' from the original corner location.

Corner research on file with Gogebic County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 2" X 30" aluminum pipe with a 3 ¼" stamped aluminum cap and the following new blazed and scribed bearing trees: (measurements taken to a 10p nail in the side of the tree)

Red Maple	9"	N.16° W.	20.23'
Sugar Maple	5"	S.86° W.	26.61'
Yellow Birch	8"	S.02° W.	16.00'
Steel sign rail	6'	S.18° W.	3.02'

Richard L. Drahn 9/27/00  
COUNTY REGISTER



Signed by Richard L. Drahn Date September 27, 2000

Surveyor's Michigan License No. 21564

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971

USFS R-17

REVISED MAY 14, 1976  
REVISED JAN., 1983  
REVISED OCT., 1985