

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
 Gogebic County } ss.

Received for record the
26th day of OCTOBER
 A. D. 2000 at 1:20 o'clock
P m., and recorded in
 Liber 8 of CORNERS

on page 43
Sammy L. Stella, Jr.
 Register of Deeds

Register of Deeds Stamp & File
 Number

For corners in

Gogebic
 (County)

Located In:

Corner Code #

1. Public Land Survey

T48 N R45 W.

J-11

T R

T R

T R

2. Property Controlling
 in Section

S T R

S T R

3. Miscellaneous
 Property in Sec.

S T R

S T R

**SURVEY &
 MONUMENTATION**

JAN 05 2001

SECTION

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

1/4 Corner 26 & 35; T.48 N., R.45 W.

I, Richard L. Drahn, in a field survey on Sept. 28, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4			3			2
3													
4	7									10			11
5													
6	18			17			16			15			14
7													
8	19			20			21			22			23
9													
10	30			29			28			27			26
11													
12	31			32			33			34			35
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt on 9/20/1848. Original bearing trees:
 Sugar 10" S.50° E. 15 links (9.90')
 Sugar 10" N.50° W. 33 links (21.78')

Kellan, Limpert & Beck, on 4/11/35, found a squared Maple stake at this location. They placed a metal location poster on the SE side of a 4" Maple tree. The stake lay SE 15 feet from the tag tree.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I restored the corner position at record bearing and distance from the remains of the two original bearing trees. The first one is a large series of root holes with black flakes of Sugar Maple wood. The second one is now a very large windthrown stump hole.

The 1935 location poster was recovered on a 12" Sugar Maple windfall bearing S.58° W., 5.1 feet. No evidence remains of the squared Maple stake.

A 7" Sugar Maple with a location poster on the west side bears N.72° W., 32.0 feet from the original corner location.


Corner research on file with Gogebic County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 30" long aluminum pipe with a 3 1/4" stamped aluminum cap and the following new bearing trees:

Sugar Maple	7"	N.72° W.	32.02'
Sugar Maple	7"	S.80° E.	26.44'
Sugar Maple	9"	S.10° W.	41.65'
Steel sign rail	6'	N.23° E.	2.28'

DEED GROUP APPROVED
Richard L. Drahn 10/25/00
 COURT REGISTRAR



Signed by Richard L. Drahn

Date October 23, 2000

Surveyor's Michigan License No. 21564

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS. JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983
 REVISED OCT., 1985