

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

Register's Office }  
 Gogebic County } ss.

Received for record the  
2<sup>ND</sup> day of OCTOBER  
 A. D. 1900 at 10:50 o'clock  
A m., and recorded in  
 Liber B of CORNERS  
 as page 36  
Ramona Collins Deputy  
 Register of Deeds

For corners in

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	<u>T48 N R45 W.</u>	<u>K-9</u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
2. Property Controlling in Section	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
3. Miscellaneous Property in Sec.	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>

**SURVEY &  
 MONUMENTATION**  
JAN 05 2001

Register of Deeds Stamp & File  
 Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_ SECTION \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Section Corner 23, 24, 25 & 26; T.48 N., R.45 W.

I, Richard L. Drahn, in a field survey on August 30, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

Original corner established by Austin Burt on 9/15/1848. Original bearing trees:

Y. Birch	10"	S.45° W.	25 links	(16.50')
Y. Birch	14"	N.46½°E.	28 links	(18.48')

Supercynski, cruiser, on 4/10/35 recovered a scribed Y. Birch laying N.50° E. 15 ft. from a Maple stake. He placed a location poster on the SW side of a 12" Maple. The Maple stake lay 8 ft. SW of his tag tree.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

I restored the corner position at record bearing and distance from the remains of the NE bearing tree. It is now a badly decayed 20-26" Yellow Birch stump. The SW B.T. has been destroyed by logging road construction. A metal detector indicates the presents of Supercynskis' location poster grown into the SW side of a 23" Sugar Maple bearing N.22° E. 12 ft. from the corner location.

Corner research on file with Gogebic County records.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

At the corner position I set a 30" long aluminum pipe with a 3 ¼" stamped aluminum cap and the following new blazed and scribed bearing trees: (distances taken to a 10p nail in the side of the B.T.)

Red Maple	10"	N.02° W.	40.18'
Red Maple twin	9"	S.46°E.	18.20'
Sugar Maple	13"	S.73° W.	43.43'
Steel sign rail	6'	S.43° W.	2.24'

*NEED COUNTY APPROVAL*  
Richard L. Drahn 9/27/00  
 COUNTY REGISTER



Signed by Richard L. Drahn Date September 23, 2000

Surveyor's Michigan License No. 21564

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971