

MAR 02 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

Received for record the
21ST day of JULY
A. D. 1999 at 1:15 o'clock
P m., and recorded in
Liber 7 of CORNERS
on page 191
Roseann Collins, Deputy
Register of Deeds

For corners in

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>48N</u> R <u>45W</u>	<u>L-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Quarter Corner 1 & 12; T.48 N., R.45 W.

I, Richard L. Drahn, in a field survey on July 18, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt on 9/18/1848. Original bearing trees:

Sugar	12"	S.70° E.	15 links	(9.90')
Maple	10"	N.76° W.	21 links	(13.86')

Corner restored by Neal Sperhake, RLS 7876 on 11/9/61 from the original Maple B.T. He set a 1" X 36" iron pipe with a 4" dia. stamped aluminum cap and the following new bearing trees:

Hemlock	13'	N.21° E.	20 links	(13.20')
Hemlock	10"	S.29° E.	39 links	(25.74')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I recovered Sperhakes monument as described at record bearing and distance from the remains of the two original B.T.s. The first is a large stump hole. The second one is now a 22" dead Red Maple with GLO blazes. Recovered Sperhakes B.T.s as:

Hemlock	20"	N.25° E.	12.92'	(new nail)
Hemlock	19"	S.29° E.	25.55'	(new nail)

Corner research on file with Gogebic County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing objects referenced:

Sugar Maple	5"	S.75° W.	27.64'
Steel sign rail	6"	N.78° E.	2.31'

DEER GROUP SURVEYORS
Richard L. Drahn 7/20/99
COUNTY REGISTER



Signed by Richard L. Drahn Date July 19, 1999

Surveyor's Michigan License No. 21564

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 26, 1971
REVISED MAY 14, 1976
REVISED JAN., 1983
REVISED OCT., 1995