

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T48 N R45 W.	L-9
	T _____ R _____	
	T _____ R _____	
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	

**SURVEY &  
 MONUMENTATION**

**JAN 05 2001**

**SECTION**

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

¼ Corner 24 & 25; T.48 N., R.45 W.

I, Richard L. Drahn, in a field survey on Sept. 26, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

B. Original corner established by Austin Burt on 9/15/1848. Original bearing trees:  
 Y. Birch 16" S.28° W. 26 links (17.16')  
 Y. Birch 8" N.12° E. 27 links (17.82')

C. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I restored the corner position at record bearing and distance from the remains of the two original bearing trees. The first is a very large windthrown stump hole. The second one is a 12-16" Yellow Birch stump decayed to well below ground line. The 1.825 chain distance east from corner to "enter Tamarack swamp, SE" checks to within 10'. The ½ mile distance east and west to monumented corners is in accord with the field notes of the original Government survey.

A location poster dated 1/20/83 on a 10" Red Maple bears N.26° E. 9.8' and a location poster dated 6/12/68 on a 10" Red Maple bears S.37° W., 6.7' from the original corner location.

Corner research on file with Gogebic County records.

D. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner location I set a 2" X 30" aluminum pipe with a 3 ¼" stamped aluminum cap and the following new blazed and scribed bearing trees: (measurements taken to a 10p nail in the side of the tree)

Red Maple	7"	N.57° W.	9.98'
Sugar Maple	7"	N.77° E.	25.06'
Sugar Maple	7"	S.16° E.	19.45'
Steel sign rail	6'	N.27° E.	2.95'

*Richard L. Drahn*  
 RICHARD L. DRAHN  
 LAND SURVEYOR  
 No. 21564



Signed by Richard L. Drahn Date September 27, 2000

Surveyor's Michigan License No. 21564

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
 REVISED MAY 14, 1976

USFS R-23

REVISED JAN., 1983  
 REVISED OCT., 1996

Register's Office }  
 Gogebic County } ss.

Received for record the  
2<sup>ND</sup> day of October  
 A. D. 2000 at 10:50 o'clock  
1 m., and recorded in  
 Liber B of CORNERS  
 on page 39  
Ramona Collins, Deputy  
 Register of Deeds

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												