

Register's Office }
 Gogebic County } ss.

Received for record the
2ND day of OCTOBER
20
 A. D. 1900 at 10:50 o'clock
A m., and recorded in
 Liber 0 of CORNERS
 on page 40
Ramona Cullum Deputy
 Register of Deeds

Register of Deeds Stamp & File
 Number

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Gogebic Located In: _____ Corner Code # _____
 (County)

1. Public Land Survey T48 N R45 W. L-11
 T _____ R _____
 T _____ R _____ SURVEY &
 T _____ R _____ MONUMENTATION

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

JAN 05 2001
 SECTION

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

¼ Corner 25 & 36; T.48 N., R.45 W.

I, Richard L. Drahn, in a field survey on Sept 12, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt on 9/14/1848. Original bearing trees:
 Tamarack 10" S.32° E. 15 links (9.90')
 Tamarack 10" N.40° W. 07 links (4.62')

Limpert, Hellan & Beck, on 4/11/35 recovered a 10' Tamarack, still scribed, laying NW 5ft. from a Spruce stake. They placed a Location poster on the SW SIDE OF A 5" Cedar ~~N~~^E, 20 feet from the Spruce stake.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I restored the corner position at record bearing and distance from the major root remains of the Tamarack bearing tree at N.40° W., 4.62'. No evidence remains of the SE bearing tree. Recovered the 1935 location poster on the SW side of a 16" Cedar bearing N.48° E., 18.0 feet from the original corner location. The 1.30 chain distance west from corner to "leave beaver meadow, SW" checks to within 6 feet. The ½ mile east and west to recovered section corners is in accord with the field notes of the original Government survey.

A 4" squared Cedar post bears S.53° E: 79 feet from the original corner location.

Corner research on file with Gogebic County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a ¾" X 48" solid aluminum rod monument with a 3 ¼" stamped aluminum cap and the following new blazed and scribed bearing trees: (measurements taken to a 10p nail in the side of the tree)

Cedar 12" N.83° E. 49.13'
 Cedar 7" S.02° W. 67.92'
 Northerly high point of a large rock bears S.78° E. 4.1 feet
 Steel sign rail 6' N.27° E. 2.12'
 Steel sign rail 6' N.88° W. 2.06'

Richard L. Drahn 9/27/00
 COUNTY REGISTER



Signed by Richard L. Drahn Date September 27, 2000

Surveyor's Michigan License No. 21564

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 25, 1971