

MAR 02 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office
Gogebic County

For corners in

Received for record the
21ST day of JULY
A. D. 1999 at 1:15 o'clock
P m., and recorded in
Liber 7 of CORNER
on page 192
Robert Collins Dwyer
Register of Deeds

<u>Gogebic</u> (County)	Located in:	Corner Code #
1. Public Land Survey	<u>T 48N R45 W.</u>	<u>M-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Section Corner 12, 13, 7 & 18; T.48 N., R.44-45 W.

I, Richard L. Drahn, in a field survey on July 16, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt on 9/9/1847. Original bearing trees:

Elm	18'	S.42 E.	28 links	(18.48')
Y. Birch	18"	N.14 W.	12 links	(7.92')

Corner restored by Donald D. Lappala, RLS 12585, on 8/9/68 from the remains of the two original bearing trees (the Y. Birch was still scribed). He set a 2" X 5' iron pipe monument with a 3" stamped brass cap and the following new bearing trees:

Yellow Birch	10"	N.89 W.	16.1'
Sugar Maple	4"	N.35 E.	19.4'
Sugar Maple	5"	S.10 E.	28.1'

Corner recorded in Gogebic County in USFS Liber, Page J-1, on 3/31/69

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I recovered the monument as described and the bearing trees as follows:

Yellow Birch (downed)		N.88 W.		
Sugar Maple	6"	N.38 E.	19.32	(new nail)
Sugar Maple	7"	S.07 E.	27.94'	(new nail)

Corner research on file with Gogebic County records.

The original Elm B.T. is now only a large windthrown depression. The original Birch B.T. is now a live 38-40" Yellow Birch. (No scribing remains).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing objects referenced:

Red Maple	12"	N.40 W.	28.23'
4"X4"X7' Cedar sign post		N.49 E.	3.35'
Steel sign rail	6'	S.27 W.	2.21'

DEED GROUP APPROVED

Richard L. Drahn 7/20/99
COUNTY REGISTER



Signed by Richard L. Drahn Date July 20, 1999

Surveyor's Michigan License No. 21564

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1985