

MAR 02 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	<u>T.48N. R.45W</u>	<u>M-10</u>
	T. R.	
	T. R.	
2. Property Controlling in Section	S. T. R.	
	S. T. R.	
3. Miscellaneous Property in Sec.	S. T. R.	
	S. T. R.	

Register's Office }
Gogebic County } ss.

Received for record the
21ST day of JULY
A. D. 1999 at 1:25 o'clock
P m., and recorded in
7 of CORNERS
on page 194
Annexia Collins, Deputa
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Quarter Corner 25 & 30; T.48 N., R.44-45 W.

I, Richard L. Drahn, in a field survey on July 17, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
Original corner established by Austin Burt on 9/8/1847. Original bearing trees:
Yellow Birch 28" S.18° W. 30 links (19.80')
Hemlock 16" N.28° E. 28 links (18.48')

Corner restored by Donald D. Lappala, RLS 12585 on 8/29/72 from the remains of the two original B.T.s. The downed Y. Birch was still scribed. He set a 2" X 5' iron pipe monument with a 3" stamped brass cap and the following new B.T.s

Sugar Maple 6" N.52° E. 10.6'
Sugar Maple 7" S.10° E. 11.9'
Sugar Maple 6" S.87° W. 33.5'
Metal sign post 6" N.45° W. 3.5'

Corner recorded in Gogebic County USFS Liber, Page T-1, on 12/9/74.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I recovered the monument as described and the bearing trees as follows:
Sugar Maple 9" N.54° E. 10.53' (new nail)
Sugar Maple 10" S.07° E. 11.71' (new nail)
Sugar Maple 9" S.88° W. 33.54 (new nail) B.T. is now dead
Steel sign rail 6' N.46° W. 3.52'

A stump hole with fragments of Yellow Birch bark and wood remain from the original Birch B.T.. The original Hemlock is now a badly decayed Hemlock stump with portions of the B.T. overgrowth still visible.

Corner research on file with Gogebic County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing tree referenced:
Sugar Maple 6" S.84° W. 47.51'

FEEL FREE TO APPROVE
Richard L. Drahn 7/20/99
COUNTY REGISTRAR



Signed by Richard L. Drahn Date July 19, 1999

Surveyor's Michigan License No. 21564

USFS T-25

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, 1971
REVISED MAY 14, 1976
REVISED JAN., 1983
REVISED OCT., 1985