SECTION

LAND CORNER RECORDATION CERTIFICA Filing Requirement of Act 74, Mich. P.A. 19

NTE 170	Received for record the 2157 day of JULY A. D. 1999 at 1775 s'clock				
	P P P P P P P P P P P P P P P P P P P	end recorded in			
	Register of Deed	s Stamp & File Number			
1 2	A B C D E	F G H I J K L			

5

8

9

For corners in Corner Code # Gogebic Located In: 1. Public Land Survey 48N R 45W T 48N R 44W A-11 2. Property Controlling in Section 3. Miscellaneous Property in Sec.

4. Lot No. , Recorded Plat 5. Private Claims Section Corner 25, 36, 30 & 31; T.48 N., R.44-45 W. , in a field survey on July 17, Richard L. Drahn _, 19<u>99</u>

__ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt on 9/8/1847. Original bearing trees:

S.62½° W. 30 links Yellow Birch 10' (19.80')14" N.55½° E. Lynn 36 links (23.76')

Corner restored by Donald D. Lappala, RLS 12585 on 8/30/72 from the remains of the two original B.T.s. He set a 2" X 5' iron pipe monument with a 3" stamped brass cap and the following new bearing trees:

Sugar Maple	10"	N.35°W.	12.51
Sugar Maple	7"	N.35° E.	23.5'
Sugar Maple	6"	S.57° E.	10.01
Metal sign post	6'	North	3.2'

Corner recorder in Gogebic County USFS Liber, Page M-11 on 12/9/74.

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I recovered the monument as described and the bearing trees as follows:

Sugar Maple	11"	N.37° W.	12.131	(new nail)
Sugar Maple	10"	N.35° E.	23.32'	(new nail)
Sugar Maple	8"	S.60° E.	10.02	(new nail)
Steel sign rail	6'	N.02° E.	3.15'	•

Fragments of Yellow Birch wood and bark remain from the Yellow Birch B.T.. Only a stump hole remain from the Lynn B.T.

Corner research on file with Gogebic County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing tree referenced: Sugar Maple S.39° W. 45.72

RICHARD L. DRAHN LAND SURVEYOR 21564

Date ___July 19,1999

Surveyor's Michigan License No.

REVISED OCT., 1995