

MAR 02 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's office }
Gogebic County } SA.

For corners in

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>48N R 45W</u>	<u>M-12</u>
	T <u> </u> R <u> </u>	
	T <u> </u> R <u> </u>	
	T <u>48N R 44W</u>	<u>A-12</u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	
	S <u> </u> T <u> </u> R <u> </u>	
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	
	S <u> </u> T <u> </u> R <u> </u>	

Received for record the
21st day of JULY
A. D. 1999 at 1:25 o'clock
P m., and recorded in
Liber 7 of CORNERS
on page 196
Remona Collins, Deputy
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Quarter Corner 36 & 31; T.48 N., R.44-45 W.

I, Richard L. Drahn, in a field survey on July 16, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt on 9/9/1847. Original bearing trees:
Spruce 10" S.31° W. 15 links (9.90')
Cedar 16" N.69° E. 15 links (9.90')

Corner restored by Donald D. Lappala, RLS 12585 on 10/20/69 from the remains of the two original bearing trees and a natural feature tie. He set a 2 1/4" X 5' iron pipe monument with a 3" stamped brass cap and the following new bearing trees:
Cedar 5" N.01° W. 28.6'
Cedar 7" N.83° E. 34.6'
Red Maple 7" S.33° E. 15.8'

Corner recorded in Gogebic County, USFS Liber, Page X-1 on 4/8/70.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I recovered the monument as described and the bearing trees as follows.
Cedar 7" N.03° W. 28.56' (new nail)
Cedar 12" N.82° E. 34.60' (new nail)
Red Maple (down) 10" S.35° E. 15.90' (new nail)

A depression remains from the original Spruce B.T. No evidence remains of the original Cedar B.T.

Corner research on file with Gogebic County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing objects referenced:
Red Maple 8" S.20° E. 5.52'
4"X4"x7' Cedar sign post S.60° W. 2.70'
Steel sign rail 6' N.44° E. 2.59'

DEED GROUP APPROVED
Richard L. Drahn 7/20/99
COUNTY REGISTER



Signed by Richard L. Drahn Date July 20, 1999

Surveyor's Michigan License No. 21564

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1978
REVISED JAN., 1983
REVISED OCT., 1995