

# SURVEY & REMONUMENTATION

AUG 08 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }  
Gogebic County } ss.

Received for record the  
11<sup>th</sup> day of JUNE  
A. D. 1997 at 10:35 o'clock  
A m., and recorded in  
Liber 6 of CORNERS  
on page 142.

*Colleen M. Richak, Deputy*  
Register of Deeds

Register of Deeds Stamp & File Number

For corners in

Gogebic  
(County)

Located In:

Corner Code #

1. Public Land Survey

T47NR	44W	A-1
T47NR	45W	M-1
T48NR	44W	A-13
T48NR	45W	M-13

2. Property Controlling in Section

S \_\_\_ T \_\_\_ R \_\_\_

3. Miscellaneous Property in Sec.

S \_\_\_ T \_\_\_ R \_\_\_  
S \_\_\_ T \_\_\_ R \_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Sec. cor. comm. to sec's. 1, 6, 31 & 36

I, John P. Goss, in a field survey on May 28, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1	●												●
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13	●												●

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt in 1847. Set post.  
Original bearing trees: Cedar 14" S 21½° E 114 links.  
Spruce 7" N 16° W 14 links.

On August 22, 1968, Donald Lappala, RLS, restored corner at recorded bearing and distance from now 18" Cedar stump with scribing visible S 21½° E - 62.7 feet. Also recovered 14" Cedar stub witness with scribing visible S 06° W - 70.7 feet. Lappala recorded this corner in Forest Service Record book in Gogebic County Register of Deeds Office. He set a 2" iron pipe with 3" bronze table indicated corner location with the from witnesses.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

12" Cedar S 76° E - 82.0'; 12" Cedar S 35° E - 46.6'  
4"x4"x7' Cedar Post S 38° E - 3.2'; 6" Cedar S 03° W - 71.2'

Found 18" Cedar Stump @ S 21½° E - 62.7' and recovered 14" Cedar stub with scribing visible @ S 06° W - 70.7'. Also found Lappala 2" iron pipe with 3" bronze table and witnesses checked. I updated the accessories as noted below to state and county specification.

Act 74 research on file.

**PEER GROUP APPROVED**  
*Richard D. Dean* 6/10/97  
COUNTY SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the 2" iron pipe with 3" bronze table stamped: T. 47-48 N., R. 44-45W.; S-1, S-6, S-31, S-36; R.L.S. 12585, 1968. I established the following existing bearing trees and existing and new reference objects.

16" Cedar	S 76° E	82.00'
17" Cedar	S 35° E	46.63'
10" Cedar	S 03° W	71.21'
4"x4"x7' Cedar Post & sign	S 38° E	3.2' (to face)
6' Rail & sign	N 33° E	1.54' (to face)

(measurement to nail in side of tree)

Signed by John P. Goss

Date May 28, 1997

Surveyor's Michigan License No. 23509

Fed. No. A-25

