

MAR 02 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Register's office }  
Gogebic County } ss.

For corners in

Gogebic  
(County)

Located In: Corner Code #

1. Public Land Survey

T48N R 46W A-5

~~T49N R 46W~~ ~~M-5~~

~~T48N R 47W~~ ~~M-5~~

R&N  
7/21/99

2. Property Controlling  
in Section

S T R

3. Miscellaneous  
Property in Sec.

S T R

S T R

Received for record the  
21<sup>st</sup> day of JULY  
A. D. 1999 at 1:25 o'clock  
P m., and recorded in  
Liber 7 of CORNERS  
page 199  
Ramona Collins Deputy  
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Section corner 7,18,12 & 13 T48N, R46-47W

I, John P. Goss, in a field survey on May 15, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by William Burt, U.S. Deputy Surveyor, in September, 1847. Original bearing trees: W. Pine 24" N 72° E 24 links (15.84'); Hemlock 10" West 9 links (5.94'); Maple 10" S 34° E 35 links (23.10'); Hemlock 20" N 22° W 32 links (21.12').

On May 22, 1975, Richard L. Drahn, RLS, found corner position marked by a 2"x2" board at recorded bearing and distance from the remains of four original bearing trees: He set a 2 1/2" iron pipe with 3" cap, stamped to indicated the corner position. He established the following reference objects:

9" Cedar N 09° W 30.3'; 12" Hemlock S 21° E 29.4';

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

5" Cedar S 76° W 20.6'; 7' Metal sign post S 32° W 2.5'.

He recorded said corner in Liber 1, page 173 of Land Corners for Gogebic Co.

Found Richard L. Drahn, monument and accessories.

Found 38" White pine stump with G.L.O. Blaze.

I updated the monument and accessories as noted below to state and county specification.

Act 74 research on file.

DEED GROUP APPROVAL  
Richard L. Drahn 7/20/99  
COUNTY REGISTER

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
From found monument I established the following new and existing reference objects:

- 13" Cedar N 09° W 30.12 ft.
- 15" Hemlock S 21° E 29.32 ft.
- 7" Cedar S 76° W 20.61 ft.
- 9" Cedar N 67° E 10.49 ft.
- 7' Metal sign post S 32° W 2.5 ft. to face

(All distance to nail in side of tree)



Signed by John P. Goss  
Surveyor's Michigan License No. 23509

Date May 15, 1999

U.S.F.S. No. J-1