

JAN 22 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Gogebic  
(County)

| Located In:        | Corner Code # |
|--------------------|---------------|
| Section 25 48N 47W | M-10          |
| T 48N R 46W        | A-10          |
| T R                |               |
| T R                |               |
| T R                |               |
| S T R              |               |
| S T R              |               |
| S T R              |               |
| S T R              |               |

- 1. Public Land Survey
- 2. Property Controlling in Section
- 3. Miscellaneous Property in Sec.

Register's Office } ss.  
Gogebic County }

Received for record the  
22<sup>ND</sup> day of DECEMBER  
A. D. 19 97 at 11:10 o'clock  
A m., and recorded in  
Liber 6 of CORNERS  
on page 310  
Ramona Collins, Deputy  
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

1/4 corner section 25 & 30, T48N, R47-46W

I, John R. Garske, in a field survey on December 11, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

|    | A  | B | C  | D | E  | F | G  | H | I  | J | K  | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 1  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 2  | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |   |   |
| 3  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 4  | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |   |   |
| 5  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 6  | 10 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |   |   |
| 7  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 8  | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |   |
| 9  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 10 | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |   |   |
| 11 |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 12 | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |   |
| 13 |    |   |    |   |    |   |    |   |    |   |    |   |   |

A. Description of original monument and accessories and/or subsequent restoration:

Original Township survey by William A. Burt in 1847.  
He set a wood post from which:  
Tamarack 18" N81°W 41 links  
Tamarack 7" S36°E 46 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found no evidence of the original survey. The corner now falls in the middle of Bale Lane, a gravel road. I found a 1/2" iron rod at the corner in the center of the road opposite an ancient fence line running east. The corner is shown on 1979 survey notes by William Riipi, RLS in a survey of the Gogebic - Iron Airport. Our distances check relatively well to known corners North - 2624.70M, 2629.57R, & South - 2652.36M, 2652.59R.

(Research on file)

**PEER GROUP APPROVED**  
Richard L. Dralun 12/19/97  
**COUNTY REPRESENTATIVE**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the found 1/2" iron rod I set two reference monuments consisting of 3/4" dia. x 3' long alum. rods with 3 1/4" dia. alum. caps stamped:  
R.M. West 37.57 feet  
Steel sign rail 1.81 feet, 39.38 ft. to corner  
R.M. East 34.59 feet  
Steel sign Rail 1.73 feet, 36.32 to corner  
Monuments are on line with corner  
Top of Steel Gate Post - S15°E 168.62 feet  
Corner is in an open area with no other bearing objects available.

Signed by John R Garske  
Surveyor's Michigan License No. 28410

Date

