

SURVEY & REMONUMENTATION

OCT 08 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Gogebic
(County)

Located In: Corner Code #

- | | | | |
|------------------------------------|-------------------------|-----------------|------|
| 1. Public Land Survey | | T 48N R 46W | A=11 |
| | | T 48N R 47W | M=11 |
| | | T _____ R _____ | |
| | | T _____ R _____ | |
| 2. Property Controlling in Section | S _____ T _____ R _____ | | |
| | S _____ T _____ R _____ | | |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | | |
| | S _____ T _____ R _____ | | |

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Sec. cor. comm. to sec's. 25, 36, 30 & 31

I, John P. Goss, in a field survey on June 14, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by William A. Burt. Set cedar Post.
Original bearing trees: Hemlock 16" S 78° W 24 links
Hemlock 30" N 85° E 32 links.

In January of 1978 split fence lines and centerline of Airport Road set a railroad spike by Ewart Muller. Ewart Muller recorded said corner position in Liber 1 on page 343. He established the following reference objects.
D.H. Nail in P.Pole- N40°W-65.91'; D.H. Nail in P.Pole- S 65° E-45.43';
D.H. Nail in P.Pole S 36° W- 39.98'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found a P.K. Nail in top of asphalt surface and a railroad spike 3 inches below top of asphalt surface and they checked witnesses in Ewart Muller certification. I Updated the corner monument and accessories as noted below to state and county specification.

Act 74 research on file.

PEER GROUP APPROVED
Richard P. Dralun 8/8/96
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At 1" below asphalt surface I set a 2½" brass cap with a 2" stem over the railroad spike. Cap is stamped T. 48 N., R.46-47 W., S-25, S-36, S-30, S-31; 1996, P.S. 23509. I established the following references objects.

- | | | |
|----------------------|---------|--------|
| D.H. Nail in P. Pole | S 65° W | 75.05' |
| D.H. Nail in P. Pole | N 40° E | 45.41' |
| D.H. Nail in P. Pole | S 42° E | 39.98' |

Reference Monument consisting of a 2½" by 30" Aluminum monument with a ¾" aluminum cap stamped to indicated corner position.
N 37° W 53.78', with 6" rail & sign 1.19'



Signed by John P. Goss

Date June 15, 1996

Surveyor's Michigan License No. 23509

Fed. No. V-1

402

Register's Office }
Gogebic County } ss.

Received for record the
16th day of AUGUST
A. D. 1996 at 10:30 o'clock
A m., and recorded in
Liber 5 of CORNERS
on page 402
Ramona Collins Deputy
Register of Deeds

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													