

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } SM.

For corners in

Gogebic
(County)

Located In: Corner Code #

1. Public Land Survey

Section	<u>T48N</u>	<u>R47W</u>	<u>A-12</u>
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

Received for record the
21ST day of JULY
A. D. 1999 at 1:25 o'clock
P m., and recorded in
Liber 7 of CORNERS
on page 197
Roma Collins, Deputy
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Quarter corner common to sections 31 & 36, T48N, R47W & R46W

I, John R. Garske, in a field survey on May 12, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original Township Survey by William A. Burt, D.S.1847.
Original bearing trees: Lynn 7" S57°-05'-5links, & Lynn 6"-N68°W-32links.
1977-Corner established by Ewart Muller, RLS 15408 by single proportion on the range line and recorded liber 1, pg. 341 he set a 1" x 3' iron pipe from which;
Witnesses;
Chisled "+" in rock Due West 55.60 feet
8" aspen S50°E 45.73 feet
Fence post N50°W 66.41 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found a bent pipe at Mullers corner position. I reset a standard Bernsten Aluminum pipe monument at the corner from two of Mullers ties, the boulder and aspen and additional ties from our survey files from a 1989 survey of the Ironwood Township Landfill.

(Research on file)

PEER GROUP APPROVED
Richard L. Drahn 7/20/99
COUNTY REGISTER

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Reset 30" x 2 1/2" alum. monument with a 3 1/4" dia stamped alum. cap from which:
Sign rail S60°E 1.12 feet
Chiseled "+" in boulder S80°W 56.00 feet (55.60')
8" W. Birch S52°E 47.05 feet
Twin 3" maple S76°E 49.15 feet

Signed by John R. Garske
Surveyor's Michigan License No. 28410

Date 7/20/99

