

MAR 02 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }  
Gogebic County }

For corners in

Gogebic

(County)

Located In:

Corner Code #

1. Public Land Survey

T48N R46W

88-5

2. Property Controlling  
in Section

S

T R

3. Miscellaneous  
Property in Sec.

S

T R

S

T R

Received for record this  
21<sup>ST</sup> day of JULY  
A. D. 1999 at 1:25 o'clock  
P. m., and recorded in  
Liber 7 of CORNERS  
page 200  
Bonnie Collins Dantz  
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

1/4 corner 7 & 18, T48N, R46W

I, John P. Goss, in a field survey on May 15, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:  
Corner established by Austin Burt, U.S. Deputy Surveyor on June 4, 1851.  
Original bearing trees: Hemlock 12" S 24° W 18 links (11.88')  
Hemlock 12" N 49° E 7 links (4.62')  
On May 22, 1975, Richard L. Drahn, RLS, found corner position marked by the decayed fragments and point of the hemlock post recovered by David Barnhart at record bearing and distance from the remains of the two original bearing trees. He set a 2 1/2" iron pipe with 3" cap, stamped to indicated the corner position. He established the following reference objects: 14" Hemlock - N 42° W - 41.2 ft. 3" Red Maple - S 75° E - 30.9 ft.; 7" Cedar - S 09° W - 33.5 ft.; 7' metal sign post - S 07° W - 1.4 ft.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.  
He recorded said corner in Liber 1, page 175 of Land Corners for Gogebic Co.  
Found Richard L. Drahn, monument and accessories.  
Found original NE bearing tree now only stump remaining.  
I updated the monument and accessories as noted below to state and county specification.  
Act 74 research on file.

DEED GROUP APPROVED  
Richard L. Drahn 7/20/99  
COUNTY REGISTER

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.  
From found monument I established the following new and existing reference objects:

- 15" Hemlock N 42° W 41.09 ft.
- 6" Red Maple S 75° E 30.96 ft.
- 10" Cedar S 09° W 33.54 ft.
- 9" Tw. Maples N 20° E 14.12 ft.
- 7' Metal sign post S 07° W 1.47 ft. to face

(All distances to nail in side of tree)

Signed by John P. Goss

Surveyor's Michigan License No. 23509

Date May 15, 1999

U.S.F.S. No. J-3

