

SURVEY & REMONUMENTATION

FEB 18 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Gogebic
(County)

Located in:

Corner Code #/

- 1. Public Land Survey Section 31T 48N R 46W Corner Code #/ B-11
 - T _____ R _____
 - T _____ R _____
 - T _____ R _____
- 2. Property Controlling in Section S _____ T _____ R _____
 - S _____ T _____ R _____
- 3. Miscellaneous Property in Sec. S _____ T _____ R _____
 - S _____ T _____ R _____

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

One-quarter corner to S-30 & 31, T48N, R46W.

I, John R. Garske, in a field survey on December 9, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original survey by Austin Burt on June 6, 1851. Set quarter post at 35.65 chs (west to east) bearing trees:

- 6" tamarack - S58°W - 26 links
- 8" tamarack - N34°E - 16 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found a 1/2" bolt head marking the one-quarter corner position. This corner location was used or set by George Wilson, RLS, in the early 1970's in surveys in the Powderhorn area. It has been used and accepted in many surveys since that time and is generally accepted by residents and used by the Gogebic County Road Commission as marking the one-quarter corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found a 1/2" bolt at intersection of two roads. Established the following bearing trees and reference objects:

- 10" tamarack - S31°W - 50.31 feet - Found wit. nail with washer.
- Power pole #151 - S35°E - 42.78 feet - Found wit. nail with washer.
- Guy pole LSDP #30-49/06 - N38°E - 46.80 feet - Found wit. nail with washer
- Reference monument - N48°W - 53.16 feet - Set standard Bernsten 3 1/2" aluminum cap stamped on one 4' section of 3/4" aluminum swamp rod with steel sign post - 0.61 feet.
- Reference monument - S50°W - 57.07 feet - Set standard Bernsten 2 1/2" x 30" aluminum monument with a 3 1/2" stamped aluminum cap, steel sign post - 1.50 feet

Signed by John R. Garske
Surveyor's Michigan License No. 28410

Date 12/21/93

Register's Office }
Gogebic County } SS.

Received for record the
30th day of DECEMBER
A. D. 1993 at 12:30 o'clock
P m., and recorded in
Liber 4 of CORNERS
on page 333
Betty Harris, Deputy
Register of Deeds

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11	•												
12	31	32	33	34	35	36							

