

SURVEY & REMONUMENTATION

JAN 22 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

Received for record the
24th day of NOVEMBER
A. D. 1997 at 11:40 o'clock
A m., and recorded in
Liber 6 of CORNERS
on page 275
Ramona Collins Deputy
Register of Deeds

SECTION

For corners in

Gogebic

(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|---------------------------|------------|
| 1. Public Land Survey | T <u>48N</u> R <u>46W</u> | <u>0-3</u> |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| 2. Property Controlling in Section | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
| 3. Miscellaneous Property in Sec. | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

S.C. comm. to Sects. 5, 6, 7 & 8, T48N, R46W

I, John P. Goss, in a field survey on Oct. 16, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3			●										
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:
Original corner established by Austin Burt on June 4, 1851. Set post.
Original bearing trees:

Elm	26"	S 48° W	8 links (5.28')
Yellow Birch	24"	East	17 links (12.22')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found Y. Birch, now a windfall with 30" to 32" stump. Blaze visible on windfall.
Found 3/4" by 48" iron pin.
Found forest tag in 11" Maple - N 34° E - 8.58' - 1984.
In 1923 Gogebic County Road found original bearing tree.

I updated the corner monument and accessories as noted below to state and county specification.

Act 74 research on file.

BEEN GROUP APPROVED
Richard P. Widom 11/11/97
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
I replaced the 3/4" iron pin with a 2 1/4" by 30" aluminum pipe with a 3 1/4" aluminum cap at the corner position which read: T.48 N., R.46 W.; S-5, S-6, S-7, S-8; 1997; P.S. 23509; County Remonumentation. I established the following bearing trees and reference object.

11" Maple	N 34° E	8.58'
13" Maple	Due South	29.33'
5" Maple	S 41° W	8.18'
6' Rail & sign	N 77° W	1.10' (to face)

(All measurement to nail in side of tree).

Signed by John P. Goss
Surveyor's Michigan License No. 23509

Date October 17, 1997

Fed. No. E-5

