

MAR 02 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office } ss.  
Gogebic County }

Received for record the  
12<sup>TH</sup> day of MAY

A. D. 1999 at 10:30 o'clock

A. m., and recorded in

Liber 7 of CORNEA

on page 143

Ramona L. Collins, De  
Register of Deeds

Register of Deeds Stamp & File Number

For corners in

Gogebic  
(County)

Located In:

Corner Code #

- 1. Public Land Survey T48<sup>N</sup>R46<sup>W</sup> C 5-8  
T\_\_\_R\_\_\_  
T\_\_\_R\_\_\_  
T\_\_\_R\_\_\_
- 2. Property Controlling S\_\_\_T\_\_\_R\_\_\_  
in Section S\_\_\_T\_\_\_R\_\_\_
- 3. Miscellaneous S\_\_\_T\_\_\_R\_\_\_  
Property in Sec. S\_\_\_T\_\_\_R\_\_\_

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

South W.C. to Sections corner, 7,8,17 & 18, T48N, R46W

I, John P. Goss, in a field survey on April 27 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:  
 Corner established by Austin Burt, U.S. Deputy Surveyor, on June 4, 1851.  
 Original bearing trees: Y. Birch 12" S 60°E 30 links (19.80')  
 Cedar 12" S 42°W 6 links (3.96')  
 This corner is on the South correction line between sections 17 & 18, located 1.25 chains South of corner. On South side of pond or marsh, course W & NE. On May 20, 1975, Richard L. Drahn, RLS, restored corner position at record bearing and distance from the remains of the two original bearing trees. He set a 2" iron pipe with 3" brass tablet, stamped to indicated the corner position. He established the following reference objects:

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 5" Cedar - N 21° E - 13.2 ft.; 7" Cedar - S 55° W - 21.0 ft.  
 6" Cedar - S 49° W - 32.8 ft.; 7" steel sign post - S 87° W - 1.5 ft.  
 He recorded said corner in Liber 1, page 175 of Land Corners for Gogebic Co. Found Richard L. Drahn monument and reference objects.  
 I updated the monument and reference objects as noted below to state and county specification.  
 Act 74 research on file.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 From found monument I established the following existing and new reference objects:

- 5" Cedar (dead) N 21° E 13.2 ft.
- 8" Cedar S 55° E 20.88 ft.
- 8" Cedar S 49° W 32.82 ft.
- 6" Cedar S 12° W 43.50 ft.
- 7' Metal sign post S 87° W 1.4 ft. to face

(All measurement to nail in side of tree)



Signed by John P. Goss  
Surveyor's Michigan License No. 23509

Date April 27, 1999

U.S.F.S. No. jk-5