

SURVEY &  
REMONUMENTATION

SEP 08 1998

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }  
Gogebic County } ss.

Received for record the  
14<sup>th</sup> day of MAY  
A. D. 1998 at 3:30 o'clock  
P m., and recorded in  
Liber 6 of CORNERS  
on page 392  
Ramona Collins Dep.  
Register of Deeds

For corners in SECTION

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>48N</u> R <u>46W</u>	<u>D-7</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_  
1/4 cor. comm. to Sec's. 17 & 20, T.48N., R.46W

I, John P. Goss, in a field survey on March 7, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7				●									
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt on June 5, 1851. Set post.  
Original bearing trees: Sugar 10" S 10° W 3 links  
Sugar 10" N 10° E 3 links.

On May 22, 1975 Richard Drahn, RLS, restored corner position at record bearing and distances from remains of original bearing trees. One a Sugar Maple stump and the second a sugar stump hole. He set a 2 1/2" iron pipe with 3" bronze cap stamped to indicated the corner position. He established the following reference objects.

- 7" Sugar Maple N 38° E 20.2'
- 5" Sugar Maple S 38° E 6.4'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 4" Sugar Maple S 70° W 7.3' (now bend over and split)
- 7' Metal sign Post S 89° W 1.9'

He recorded said corner in Liber 1, page 176 of Land Corners for Gogebic County Found Richard Drahn corner monument and witnesses.

I updated the corner monument and accessories as noted below to state and county specification.

Act 74 research on file.

PEER GROUP APPROVAL  
Richard R. Drahn 5/13/98  
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the 2 1/2" iron pipe with 3" bronze cap which read: T.48 N., R.46 W.; 1/4; S-17, S-20, R.L.S. 21564; 1975, from which I established the existing and new bearing trees and reference objects.

- 8" Sugar Maple N 38° E 20.30'
- 6" Sugar Maple S 33° E 6.47'
- 5" Sugar Maple S 61° W 16.34'
- 7' Metal Sign Post S 89° W 1.9' (to face)

(All measurement to nail in side of tree)

Signed by John P. Goss  
Surveyor's Michigan License No. 23509

Date 4/1/98

Fed. No. N-7

