

SURVEY & REMONUMENTATION

FEB 18 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

Received for record the
30th day of December
A. D. 1993 at 12:30 o'clock
P m., and recorded in
Liber 4 of CORNERS
on page 334
Betty Harris Deputy
Register of Deeds

For corners in	Located In:	Corner Code #
<u>Gogebic</u> (County)		
1. Public Land Survey	T <u>48N</u> R <u>46W</u>	<u>D-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____
One-quarter corner S-29 & 32, T48N, R46W.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John R. Garske, in a field survey on December 13, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
Austin Burt, U.S.D.S., in 1851 set wood post at 39.61 chs from which a 10" Y. birch bears S18°E, 35 links and a 12" hemlock bears N28°W, 29 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
No original evidence found due to road and utility construction. Reestablished corner from the recorded plat of upland meadows subdivision, using found concrete monuments within the plat.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Set a 3/4" x 30" rebar with 3 1/2" aluminum county cap stamped: County Remonumentation; T48N, R46W; 1/4 cor.; S-29; S-32; 1993; RLS 28410. Corner position is located at the intersection of Rooni Lane and Sandene Road (4" below gravel road surface). Established the following bearing trees and/or reference objects:

- 3" concrete monument with 5/8" rebar and aluminum county cap
- Reference monument - due south - 33.00 feet A.K.A. N.E. corner of said plat
- 4" R. pine - N38°W - 64.45 feet
- Fence corner post - N25°E - 88.76 feet
- 10" R. pine - S64°E - 87.79 feet
- Reference monument - S52°W - 42.55 feet - Set a 2 1/2" x 30" Bernstein aluminum monument with a 3 1/2" stamped aluminum cap - steel sign post - 1.39 feet



Signed by John R. Garske Date 12/21/93
Surveyor's Michigan License No. 28410