

MAR 02 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's office }
Gogebic County } ss.

Received for record the
21ST day of JULY
A. D. 1999 at 1:25 o'clock
P m., and recorded in
Liber 7 of CORNERS
on page 202
Rosemary Collins, Deputy
Register of Deeds

For corners in

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	<u>T48N R 46W</u>	<u>E-6</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Quarter Corner, Sections 16 & 17, T48N, R46W

I, John P. Goss, in a field survey on July 2, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	10		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt, on June 2, 1851.

Original bearing trees: Black Cherry 12" N 57° W 13 links (8.58 ft.)
Sugar 14" S 81° E 26 links (17.16 ft.)

On June 8, 1981, Richard L. Drahn, found corner position marked by a 3" sward maple picket at record distance and bearing from the remains of the two original bearing trees. He set a 2" aluminum monument with 3/4" aluminum cap, stamped to indicated corner position. He established the following reference objects:
14" Sugar Maple N 74° W 19.16 ft.; 10" Sugar Maple N 44° E 16.78 ft.;
10" Sugar Maple S 21° W 21.26 ft.; 7' metal sign post S 88° E 1.9 ft.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

He recorded said corner in Liber 2, page 258 of Land Corners.

No original evidence found.

Found Richard L. Drahn, monument and accessories.

Act 74 research on file.

PEER GROUP APPROVED

Richard L. Drahn 2/20/99
COUNTY REGISTER

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the found monument I established the following new and existing reference objects.

16" Sugar Maple	N 74° W	19.03 ft.	new nail
14" Sugar Maple	N 44° E	17.07 ft.	new nail
15" Sugar Maple	S 21° W	21.34 ft.	new nail
9" Sugar Maple	S 55° E	22.85 ft.	
7' metal sign post	S 88° E	1.9 ft.	to face

(All measurement to nail in side of tree)



Signed by John P. Goss
Surveyor's Michigan License No. 23509

Date July 2, 1999

U.S.F.S. No. L-9