

SURVEY & REMONUMENTATION

JAN 22 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

Received for record the
22ND day of DECEMBER
A. D. 1997 at 11:00 o'clock
A m., and recorded in
6 of CORNERS
on page 300
Ramona Collins, Deputy
Register of Deeds

For corners in
Gogebic

Located In:	Corner Code #
Section 28 48N 46W	E-10
T ___ R ___	_____
T ___ R ___	_____
T ___ R ___	_____
T ___ R ___	_____
S ___ T ___ R ___	_____
S ___ T ___ R ___	_____
S ___ T ___ R ___	_____
S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

- 1. Public Land Survey
- 2. Property Controlling in Section
- 3. Miscellaneous Property in Sec.

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

1/4 corner sections 28 & 29, T48N, R46W

I, John R. Garske, in a field survey on December 3, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original Township survey by Austin Burt, Deputy Surveyor in 1851.
He set a wood post from which:
Yellow Birch 8" S84°E 23 links
Hemlock 8" N 68°W 23 links


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence exists. I established the corner at the centerline intersection of Hedberg Road and a ancient fence line extended from the east. This corner position checks with local occupation/fence lines and is the most logical position for the 1/4 corner.

(Research on file)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 5/8" x 10" iron rod with a 3 1/4" brass cap stamped to identify the corner, from which:
Reference Monument (R.M.) Due West 30.83 feet Steel Sign Rail
Power Pole S30°W 55.75 feet
8" Spruce N84°E 54.98 feet
4" Fence Post N30°W 61.00 feet
Section corner 28, 29, 32 & 33 Due South 2643.67 feet



PEER GROUP APPROVED

Richard L. Decker 12/19/97
GOVERNOR

Signed by John R. Garske
Surveyor's Michigan License No. 28410

Date 12/19/97