

NOV 12 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

Received for record the
18th day of AUGUST
A. D. 1997 at 11:00 o'clock
A m., and recorded in
Liber 6 of CORNERS

on page 191
Ramona Collins Deputy
Register of Deeds

Register of Deeds Stamp & File Number

For corners in <u>Gogebic</u> (County)	Located in:	Corner Code #
1. Public Land Survey	<u>T48NR46W</u>	<u>E-11</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

4. Lot No. , Recorded Plat
5. Private Claims

I, John P. Goss, in a field survey on July 23, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

E-11 Corner of Sections 28, 29, 32 & 33, T48N, R46W

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt, on June 5, 1851. Set post.

Original bearing trees:

Y. Birch	16"	S 58° W	55 links
Sugar	18"	N 35° E	22 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence found, due to road construction. Corner was re-established at road centerline intersection which check with fence lines West, East and South. A 1932 survey by Gogebic County Road Commission show location of corner in center of intersection.

I accepted this as best position for section corner and have monumented it as such.

Act 74 research on file.

PEER GROUP APPROVED
Richard H. Decker 8/13/97
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At 2" below asphalt surface I set a 2 1/2" brass cap with 2" stem over a 1/2" rebar. The brass cap is stamped T.48 N., R.46 W.; S-28, S-29, S-32, S-33; 1997; P.S.23509. I established the following bearing trees and reference objects.

P. Pole #82-90/96	S 55° W	32.87'
T. Pole	N 46° E	30.85'
6" Aspen	S 30° E	65.27'

Reference Monument consisting of 2 1/2" x 30" aluminum monument with 3/4" aluminum cap stamped to indicate corner position. N 62° W - 49.67' with 6' rail & sign 0.88' (All measurement to nail in side of tree & poles)

Signed by John P. Goss

Date July 23, 1997

Surveyor's Michigan License No. 23509

Fed. No. V-9

