

MAR 02 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

Received for record the
21st day of JULY
A. D. 1999 at 1:25 o'clock
P m., and recorded in
Liber 7 of CORNER
page 203
Romona Collins DePinto
Register of Deeds

Register of Deeds Stamp & File Number

For corners in

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>48</u> ^N R <u>46</u> ^W	<u>F-7</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____
1/4 corner 16 & 21, T48N, R46W

I, John P. Goss, in a field survey on May 18, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:
Corner established by Austin Burt on 5/31/1851
Original B.T's Sugar 12" S 33° E 11 links (7.26 ft.)
Sugar 12" N 33° W 31 links (20.46 ft.)

On Aug. 13, 1979, Richard L. Drahn, RLS, restored corner position at record bearing and distance from the remains of the two original bearing trees. He set a 2" x 5' iron pipe with 3" brass cap, stamped to indicated the corner position. He established the following reference objects:
5" Basswood S 85° W 22.85 ft.; 8" Red Maple N 18° E 30.9 ft.;
9" S. Maple S 21° E 40.75 ft.; 7' Metal sign post N 89° E 1.65 ft.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
He recorded said corner in Liber 2, page 25 of Land Corners for Gogebic Co.

Found Richard L. Drahn, monument and accessories.

I updated the monument and accessories to state and county specification as noted below.

Act 74 research on file.

PEER GROUP APPROVED
Richard L. Drahn 7/20/99
COUNTY REGISTER

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
From found monument I established the following new and existing reference objects:

8" Basswood	S 85° W	22.83 ft.
12" Red Maple	N 18° E	30.93 ft.
12" Sugar Maple	S 21° E	40.75 ft.
5" Tw. Maple	N 39° W	29.28 ft.
7' Metal sign post	N 89° E	1.65 ft. to face

(All measurement to nail in side of tree)



Signed by John P. Goss
Surveyor's Michigan License No. 23509

Date May 18, 1999

U.S.F.S. No/ N-11