

NOV 12 1997

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }  
 Gogebic County } ss.

For corners in

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	<u>T48NR46W</u>	<u>F-11</u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
2. Property Controlling in Section	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
3. Miscellaneous Property in Sec.	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>

Received for record the  
18<sup>th</sup> day of CORNELIUS  
 A. D. 1897 at 11:00 o'clock  
A M., and recorded in  
 Liber 6 of CORNELIUS  
 on page 192  
Ramona Collins Deputy  
 Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, John P. GOSS, in a field survey on Aug. 6, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1/4 cor. comm. to sec's 28 & 33, T48N, R46W = F-11

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt, on June 5, 1851. Set post.  
 Original bearing trees:

Hemlock 10" S 54° E 41 links  
 Hemlock 14" N 53° W 33 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence found, due to road construction in area.  
 I re-established the corner in the centerline of Sandene Road and midway between the Section corners East and West.

Act 74 research on file.

**PEER GROUP APPROVED**  
Richard L. Nelson 8/13/97  
 COUNTY      REGISTERED

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a P.K. Nail in centerline of Sandene Road, referenced by two monuments consisting of 2½" x 30" aluminum with 3½" aluminum cap stamped to indicate corner position. I established the following bearing tree and reference objects.

P.Pole # 33-52/96 S 06° E 35.15'  
 21" W. Pine N 16° W 92.71'  
 R.M. N 37° E 38.88' with 6' rail & sign- 1.33'  
 R.M. S 31° W 40.35' with 6' rail & sign- 1.25'

(All measurement to nail in side of tree & pole)

Signed by John P. Goss  
 Surveyor's Michigan License No. 23509

Date August 6, 1997

Fed. No. V-11

