

MAR 02 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Gogebic

(County)

Located In:

Corner Code #

1. Public Land Survey

T48N R46W

G-6

T R

T R

T R

T R

2. Property Controlling
in Section

S

T R

S

T R

3. Miscellaneous
Property in Sec.

S

T R

S

T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

1/4 corner 15 & 16, T48N, R46W

I, John P. Goss, in a field survey on May 24, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on June 4, 1851.

Original B.T.'s: Fir 10" S 30° E 10 links (6.60')
Cedar 12" N 46° W 19 links (12.54')

On March 14, 1979, Richard L. Drahn found correct corner position marked by portion of a 3" Sq. cedar picket in a mound of stones at record bearing and distance from the remains of the cedar bearing tree. He set a 2" x 5' iron pipe with 3" brass cap stamped to indicated the corner position. He established the following references objects: 13" Cedar - S 47° W - 27.5 ft.; 9" Cedar (down) N 14° W - 6.45 ft.; 5" Cedar (Down) N 82° E - 25.55 ft.; 10" Black Ash - N 82° E 27.3 ft.;

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
7' metal sign post - N 87° E - 1.3 ft.

He recorded said corner in Liber 2, page 27 of Land Corners for Gogebic Co.
Found Richard L. Drahn, monument and accessories.

Act 74 research on file.

DEED GROUP APPROVED
Richard L. Drahn 7/20/99
COURT RECORDED

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From found monument I established the following new and existing reference objects:

16 Cedar S 47° W 28.20 ft. new nail
12" Black Ash N 82° E 27.47 ft. new nail
9" Black Ash S 61° E 14.13 ft.
7' metal sign post N 87° E 1.3 ft. to face

(All measurement to nail in side if tree)

Signed by John P. Goss

Surveyor's Michigan License No. 23509

Date May 24, 1999

U.S.F.S. No. L-13

Register's office }
Gogebic County } ss.

Received for record the
21st day of JULY
A. D. 1999 at 1:25 o'clock
P m., and recorded in
Liber 7 of CORNER
on page 204.
Ramona Collins Deane
Register of Deeds

Register of Deeds Stamp & File Number

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|---|----|---|----|---|----|---|----|---|----|---|----|---|
| 1 | | | | | | | | | | | | | |
| 2 | | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | | |
| 4 | | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | | |
| 6 | | 18 | | 17 | | 16 | ● | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | | |
| 8 | | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | | |
| 10 | | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | | |
| 12 | | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | | |

