

FEB 18 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Gogebic
(County)

Located In:

Corner Code #

- | | | | | | |
|------------------------------------|---|------------|---|------------|-------------|
| 1. Public Land Survey Section 34 | T | <u>48N</u> | R | <u>46W</u> | <u>G-11</u> |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous Property in Sec. | S | | T | R | |
| | S | | T | R | |

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Section corner common to S-27, 28, 33 & 34, T48N, R46W.

I, John R. Garske, in a field survey on December 9, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules theretofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original survey by Austin Burt on May 31, 1851. Set post corner from which a 12" Y. birch bears S45°E, 43 links and a 12" elm bears N45°W, 33 links.

No original evidence found.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner position was set at the center line/center line intersection of North Moore Road and Sandene Road. The position is consistent with old fence lines in the area and is shown at this location on a 1920's era Soo Line Railroad map. Measurements taken south to the railroad and the Black River confirm the center line location of this corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced a found P.K. nail at intersection of two roads with an 8 inch cotton spike set below road grade. Established the following bearing trees and reference objects:

- Power pole #25 - S46°W - 44.28 feet
- Unused power pole #MBT02 - N41°W - 45.30 feet
- Reference monument - N50°E - 45.00 feet. Set standard Bernsten 2 1/2" aluminum pipe x 30" with 3 1/2" aluminum cap stamped with steel sign post, 1.01 feet
- Reference Monument - S42°E - 50.40 feet. Set standard Bernsten 2 1/2" aluminum pipe x 30" with 3 1/2" aluminum cap stamped with steel sign post, 1.97 feet

Signed by John R. Garske
Surveyor's Michigan License No. 28410

Date 12/20/93

Register's Office }
Gogebic County } ss.

Received for record the
30th day of DECEMBER
A. D. 1993 at 12:30 o'clock
P m., and recorded in
Liber 4 of CORNERS
on page 335
Betty Sassi Deputy
Register of Deeds

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

