

MAR 08 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }  
Gogebic County } ss.

Received for record the  
12<sup>th</sup> day of MAY  
A. D. 1999 at 10:20 o'clock  
4 m., and recorded in  
Liber 7 of CORNERS  
on page 145  
Lamona Collins Deputy  
Register of Deeds

Register of Deeds Stamp & File Number

For corners in

Gogebic  
(County)

Located In:

Corner Code #

1. Public Land Survey		T <u>48</u> N R <u>46</u> W	H-9
		T___ R___	_____
		T___ R___	_____
		T___ R___	_____
2. Property Controlling in Section	S___	T___ R___	_____
	S___	T___ R___	_____
3. Miscellaneous Property in Sec.	S___	T___ R___	_____
	S___	T___ R___	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

1/4 corner, Sections 22 & 27, T48N, R46W

I, John P. GOSS, in a field survey on May 3, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L
1											
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt, U.S. Deputy Surveyor, on May 30, 1851.  
Original bearing trees: Sugar 12" S 19° W 14 links (9.24')  
Hemlock 12" N 17° E 23 links (15.18')

On Aug. 24, 1979, Richard L. Drahn, RLS, restored corner position at record bearing and distance from the remains of the two original bearing trees. He set a 2" iron pipe with 3" Brass tablet, stamped to indicate the corner position. He established the following reference objects: 10" S. Maple - N 09° W - 21.7'; 8" S. Maple - S 72° E - 44.9'; 4" S. Maple - S 55° W - 15.6'; 7' metal sign post - N 45° E - 1.9'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

He recorded said corner in Liber 2, Page 35 of Land Corners for Gogebic County.

Found Richard L. Drahn, monument and reference objects.

I updated the monument and accessories as noted below to state and county specification.

Act 74 research on file.

PEER GROUP APPROVED  
Richard L. Drahn 5/11/99  
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the found monument I established the following existings and new reference objects:

15" Sugar Maple	N 09° W	21.77 ft.	new nail
9" Sugar Maple	S 72° E	44.85 ft.	
5" Sugar Maple	S 55° W	15.64 ft.	
6" Sugar Maple	N 21° E	17.13 ft.	
7' metal sign post	N 45° E	1.9 ft.	to face

(All measurement to nail in side of tree)



Signed by John P. Goss  
Surveyor's Michigan License No. 23509

Date May 3, 1999

U.S.F.S. No. R-15