

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

Register's Office }  
 Gogebic County } ss.

For corners in

Gogebic  
(County)

Located In:

Corner Code #

Received for record the  
21<sup>st</sup> day of SEPTEMBER  
 A. D. 1995 at 9:55 o'clock  
A m., and recorded in  
 Liber 5 of CORNERS  
 on page 294  
Ramona Collins, Deputy  
 Register of Deeds

Register of Deeds Stamp & File Number

- |                                    |                           |              |
|------------------------------------|---------------------------|--------------|
| 1. Public Land Survey              | T <u>47N</u> R <u>46W</u> | H- <u>1</u>  |
| <u>S-3</u>                         | <u>48N</u> R <u>46W</u>   | H- <u>13</u> |
|                                    | T _____ R _____           | _____        |
|                                    | T _____ R _____           | _____        |
| 2. Property Controlling in Section | S _____ T _____ R _____   | _____        |
|                                    | S _____ T _____ R _____   | _____        |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____   | _____        |
|                                    | S _____ T _____ R _____   | _____        |

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

One-quarter corner common to Sections 3 and 34, T47N, 48N, R46W.

I, John R. Garske, in a field survey on August 23, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

On September 9, 1847, William A. Burt set a yellow birch post from which a 8" sugar bears N46°E, 13 links and a 20" yellow birch - N86°W, 14 links.

Survey by John Garske for Great Lakes Gas Transmission Co. on 2-22-90 found a 1" I.D. iron pipe in the center of Stone Road, from which a 4" sugar bears S48°E, 54.57 feet and a 8" and 4" twin sugar with a Marathon County tag - S31°W, 51.41 feet and a fence post - South 37.0 feet. Iron pipe was used in survey of the Bessemer sewage lagoon site by Beecher-Hoppe Engineering Co.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Found 1" I.D. iron pipe as described above and accepted as being in the correct position as it has been used in several surveys. Distance checks east and west to existing corners were used in verifying this position.

Corner record research on file with County Register of Deeds.



**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

A 1" I.D. iron pipe marks the corner position. I established the following bearing trees and/or reference objects:

- 10" maple - S31°W, 51.37 feet
- Power pole - N46°W, 59.48 feet
- 2 reference objects consisting of a 2 1/2" diameter x 30" long aluminum monument with a 3 1/4" diameter aluminum cap stamped: County Remonumentation; T48-47N; R46W; S-34; S-3; 1995; 1/4; RLS 28410.
- RM#1 - N02°W, 31.34 feet with a 6' steel rail and sign 1.12 feet away
- RM#2 - S01°W, 27.38 feet with a 6' steel rail and sign 0.95 feet away

SEE SKETCH ON BACK

**PEER GROUP APPROVED**  
Ronald H. ... 9/20/95  
 COUNTY REPRESENTATIVE

Signed by John R. Garske Date 9-15-95

Surveyor's Michigan License No. 28410

# SKETCH

