

MAR 02 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

Received for record the
22ND day of SEPTEMBER
A. D. 1999 at 1:00 o'clock
P m., and recorded in
Liber 7 of CORNER
on page 249
Ravenna Collins Depitt
Register of Deeds

For corners in

Gogebic

(County)

Located in:

Corner Code #

- 1. Public Land Survey T48^N R 46^W I-5
T ___ R ___
T ___ R ___
T ___ R ___
- 2. Property Controlling S ___ T ___ R ___
in Section S ___ T ___ R ___
- 3. Miscellaneous S ___ T ___ R ___
Property in Sec. S ___ T ___ R ___

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Section corner 10, 11, 14 & 15, T.48 N., R.46 W

I, John P. Goss, in a field survey on Sept. 1 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L
2		6		5		4		3		2		1
3												
4		7		8		9		10		11		12
5									●			
6		18		17		16		15		14		13
7												
8		19		20		21		22		23		24
9												
10		30		29		28		27		26		25
11												
12		31		32		33		34		35		36
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt, on May 28, 1851.

Original bearing trees: Hemlock 8" S 38° W 15 links (9.90 ft.)
Hemlock 8" N 37° E 22 links (14.52 ft.)

Richard L. Drahn, 21564, on October 17, 1979, restored corner position at record bearing and distance from the remains of the two original bearing trees. He set a 2" iron pipe with 3" brass tablet, stamped to indicated the corner position. He established the following reference objects: 5" S. Maple - S52°E 33.0 ft.; 8" R. Maple - S 63° W - 31.7 ft. (Now down); 6" Y. Birch - N 17° W 30.8 ft.; 6" metal sign - S 48° E - 2.4 ft.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

He recorded said corner in Liber 2, page 37 of Land Corners.

Found Richard L. Drahn monument and accessories.

No original evidence found at this time.

Act 74 research on file.

DEER GROUP APPROVED
Richard L. Drahn 9/21/99
COUNTY REGISTER

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the found monument I established the following new and existing reference objects:

- 5" Sugar Maple S 52° E 33.0 ft. (Stub now)
- 9" Yellow Birch N 17° W 30.83 ft.
- 10" Yellow Birch S 68° E 16.63 ft.
- 6" Maple S 05° W 22.51 ft.
- 6' Metal sign post S 48° E 2.4 ft. to face

(All measurement taken to nail in side of tree)



Signed by John P. Goss
Surveyor's Michigan License No. 23509

Date Sept. 1, 1999

U.S.F.S. No. J-17