

MAR 02 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }  
Gogebic County } ss.

For corners in

Gogebic  
(County)

Located In:

Corner Code #

1. Public Land Survey	T48 <sup>N</sup> R46 <sup>W</sup>	I-7
	T___R___	_____
	T___R___	_____
	T___R___	_____
2. Property Controlling in Section	S___T___R___	_____
	S___T___R___	_____
3. Miscellaneous Property in Sec.	S___T___R___	_____
	S___T___R___	_____

Received for record the  
21<sup>ST</sup> day of JULY  
A. D. 1999 at 1:35 o'clock  
P. M., and recorded in  
Liber 7 of CORNERS  
on page 207.  
*Ramona Collins Deputy*  
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Section Corner 14,15,22 & 23, T48N, R46W

I, John P. GOSS, in a field survey on May 19, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on May 27, 1851.

Original B.T.'s: Y. Birch 22" S 78° W 26 links (17.16 ft.)  
Elm 24" N 48° E 40 links (26.40 ft.)

On June 22, 1979, Richard L. Drahn, RLS, restored corner position at record bearing and distance from the remains of the two original bearing trees. He set a 2" x 5' iron pipe with 3" brass cap stamped to indicated the corner position. He established the following reference objects:

8" S. Maple - N 26° W - 21.35 ft.; 6" S. Maple - S 84° E - 19.7 ft.  
9" Y. Birch - S 57° W - 21.75 ft.; 7' Metal sign post - N 09° W - 1.9 ft.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

He recorded said corner in Liber 2, page 41 of Land Corners for Gogebic Co.

Found Richard L. Drahn, monument and accessories.

Act 74 research on file.

DEER GROUP APPROVED

*Richard L. Drahn* 7/20/99  
COUNTY REGISTER

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From found monument I established the following reference objects. (some new and some existing):

11" Sugar Maple N 26° W 21.35 ft.  
8" Sugar Maple S 84° E 19.72 ft.  
11" Yellow Birch S 57° W 21.75 ft.  
10" Maple N 37° E 34.45 ft.  
7' Metal sign post N 09° W 1.9 ft. to face

(All measurement to nail in side of tree)



Signed by John P. Goss

Date May 19, 1999

Surveyor's Michigan License No. 23509

U.S.F.S. No. N-17