

MAR 02 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }  
Gogebic County } ss.

For corners in

Gogebic  
(County)

Located in:

Corner Code #

- 1. Public Land Survey      T48N R 46W      I-8
- T      R      \_\_\_\_\_
- T      R      \_\_\_\_\_
- T      R      \_\_\_\_\_
- 2. Property Controlling    S      T      R      \_\_\_\_\_
- in Section                S      T      R      \_\_\_\_\_
- 3. Miscellaneous          S      T      R      \_\_\_\_\_
- Property in Sec.        S      T      R      \_\_\_\_\_

Received for record the  
21<sup>ST</sup> day of JULY  
 A. D. 1999 at 1:25 o'clock  
P m., and recorded in  
 Liber 7 of CORNERS  
 on page 208  
Ramona Collins Deputy  
 Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

1/4 corner 22 and 23, T48N, R46W

I, John P. Goss, in a field survey on May 13, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22	●	23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:  
 Corner established by Austin Burt, U.S. Deputy Surveyor on May 29, 1851.  
 Original bearing trees: Sugar (no diameter) S 86° E 33 links (21.78')  
                                   Y. Birch (no diameter) West 02 links (1.32')  
 On Aug. 24, 1979, Richard L. Drahn, RLS, restored corner at record bearing and distance from the remains of the two original bearing trees. He set a 2" iron pipe with 3" cap stamped to indicated the corner position. He established the following reference objects: 5" S. Maple (now wind fall) - N 52° W - 11.45 ft.; 8" S. Maple - N 47° E - 27.65 ft.; 10" S. Maple - S 42° W - 19.8 ft.; 7' metal sign post - N 79° W - 1.5 ft.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 He recorded said corner in Liber 2, page 47 of Land Corners for Gogebic Co.  
 Found Richard L. Drahn monument and accessories.  
 Found original Sugar bearing tree, now a 20" dead tree with original blazes still evident.  
 I updated the monument and accessories to state and county specification as noted below.  
 Act 74 research on file.

DEED GROUP APPROVED  
Richard L. Drahn 7/20/99  
 COUNTY REGISTER

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
From found monument I established the following new and existing reference object:

- 10" Sugar Maple      N 47° E      27.65 ft.
- 12" Sugar Maple      S 42° W      19.83 ft.
- 12" Maple            S 49° E      23.81 ft.
- 7' Metal sign post    N 79° W      1.5 ft. to face

( All measurement taken to nail in side of tree)



Signed by John P Goss  
Surveyor's Michigan License No. 23509

Date May 13, 1999

U.S.F.S. No. P-17