

MAR 02 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

For corners in

Gogebic
(County)

Located in:

Corner Code #

- 1. Public Land Survey T 48N R 46W I-10
 T ___ R ___ ___
 T ___ R ___ ___
 T ___ R ___ ___
- 2. Property Controlling S ___ T ___ R ___ ___
 in Section S ___ T ___ R ___ ___
- 3. Miscellaneous S ___ T ___ R ___ ___
 Property in Sec. S ___ T ___ R ___ ___

Received for record the
12th day of MAY
A. D. 1999 at 10:20 o'clock
A m., and recorded in
Liber 7 of CORNERS
on page 147
Ramona Collins Deputy
Register of Deeds

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Quarter Section Corner, Sections 26 & 27, T48N, R46W

I, John P. Goss, in a field survey on May 1, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
Corner established by Austin Burt, U.S. Deputy Survey, on May 29, 1851.
Original bearing trees: Y. Birch 8" S 07°W 9 links (5.94')
 Hemlock 6" N 05°E 8 links (5.28')
On July 3, 1984, Richard L. Drahn, RLS, restored corner positions from found 4" squared hardwood picket at record bearing and distance from the remains of the two original bearing trees. He set a 2" aluminum monument with a 3/4" aluminum cap, stamped to indicate the corner position. He established the following reference objects: 18" Hemlock - S 89° W - 37.58'; 7" Yellow Birch - N 21° E - 41.42'; 4" Sugar maple - S 43° E - 23.63'; 6' Steel sign post - S 54° E - 2.2'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
He recorded said corner in Liber 2, page 679 of Land Corners for Gogebic Co.
Found Richard L. Drahn Monument and reference objects.

I updated the monument and accessories as noted below to state and county specification.

Act 74 research on file.

PEER GROUP APPROVED
Richard L. Drahn 5/11/99
COUNTY REGISTERED SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
From found monument I established the following existing and new reference objects:

- 19" Hemlock S 89° W 37.58 ft.
- 9" Yellow Birch N 21° E 41.42 ft.
- 5" Sugar Maple S 43° E 23.68 ft. new nail
- 11" Maple S 24° W 22.96 ft.
- 6' steel sign post S 54° E 2.2 ft. to face

(All measurement to nail in side of tree)



Signed by John P. Goss
Surveyor's Michigan License No. 23509

Date May 1, 1999.

U.S.F.S. No. T-17