

MAR 02 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

Received for record the
12th day of MAY
A. D. 1999 at 10:20 o'clock
A m, and recorded in
Liber 7 of CORNERS
on page 148
Pamona Collins, Deput
Register of Deeds

For corners in

Gogebic
(County)

Located in:

Corner Code #

- 1. Public Land Survey T48^NR46^W I-11
T___R___
T___R___
T___R___
- 2. Property Controlling in Section S___T___R___
S___T___R___
- 3. Miscellaneous Property in Sec. S___T___R___
S___T___R___

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Section Corner, Sections 26, 27, 34 & 35, T48N, R46W

I, John P. Goss, in a field survey on April 27 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by: Austin Burt, US Deputy Survey on May 29, 1851
 Original bearing trees: Sugar 10" S 57° E 28 links (18.48')
 Cedar 8" N 40° W 18 links (11.88')

On May 21, 1987, Richard L. Drahn, RLS, USFS, restored corner position by retracement measurement, east and north to recovered corner positions and line tree remains. He set a 2½" iron pipe with 3" brass cap, buried 12". He established the following reference objects: 8" S. Maple-N06°W-68.26'; 16" R. Maple-S71°E-21.12'; 5" S. Maple-S32°W-37.07'; 2" aluminum reference monument - South- 21.21'; 6' steel sign post-South-22.7'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

He recorded said corner in Liber 3, Page 64 of Land Corners for Gogebic County
 Found Richard L. Drahn monument and reference objects.

I updated the monument and accessories as noted below to state and county specification.

Act 74 research on file.

PEER GROUP APPROVED
Richard L. Drahn 5/11/99
 COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
From the found monument I established the following existing and new reference objects. Cap on monument indicate corner position:

- 11" Sugar Maple N 06° W 68.26 ft.
- 19" Red Maple S 71° E 20.80 ft. new nail
- 5" Sugar Maple S 32° W 37.07 ft.
- 14" Hemlock N 34° W 40.64 ft.
- R.M. South 21.20 ft.
- 6' steel sign post South 22.7 ft.

(All measurement to nail in side of tree)



Signed by John P. Goss
 Surveyor's Michigan License No. 23509

Date April 27, 1999

U.S.F.S. No. V-17