

Register's Office }  
Gogebic County } ss.

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Received for record the  
30<sup>th</sup> day of DECEMBER  
A. D. 1993 at 12:30 o'clock  
P. M., and recorded in  
Liber 4 of COGNERS  
on page 342  
Betty Harris Deputy  
Register of Deeds

For corners in  
Gogebic  
(County)

Located In: Corner Code #

- 1. Public Land Survey Section 3 T 47N R 46W I-1  
T R  
T R  
T 48N R 46W I-13
- 2. Property Controlling S T R  
in Section S T R
- 3. Miscellaneous S T R  
Property in Sec. S T R

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat

5. Private Claims

Section corner common to S-2 & S-3, T47N, R46W and  
S-34 & S-35, T48N, R46W.

I, John R. Garske, in a field survey on December 27, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

|    | A  | B  | C  | D  | E  | F  | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |   |

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Survey by William A. Burt on September 9, 1847. Set sugar post from which a 20" sugar bears - N62°E - 34 links and an 8" hemlock bears N57°W - 29 links and a 10" sugar bears S65°W - 19 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence found. Found a 6" nail at the intersection of a two-track road to north and an old North-South fence line to the south and at the center line of Stone Road. This corner position has been used in several surveys and is generally accepted as the most probable location of the original section corner by both local surveyors and area residents. Due to the history of the corner location and its general use and acceptance, I am accepting it as marking the true section corner location.

PEER GROUP APPROVED  
Richard R. [Signature] 4/6/95  
COUNTY REPRESENTATIVE



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced the nail with a 3/4" x 30" iron rod with a stamped 3 1/2" diameter aluminum cap from which I established the following bearing trees and reference objects:

- 18" apple - S39°E - 40.36 feet
- 5" basswood - N19°W - 34.40 feet
- Reference monument - N25°E - 34.89 feet. Set 2 1/2" x 30" aluminum County Monument with a 3 1/2" stamped aluminum cap - steel sign post - 1.33 feet.
- Reference monument - S57°W - 47.78 feet. Set 2 1/2" x 30" aluminum County Monument with a 3 1/2" stamped cap - steel sign post - 1.96 feet.

Signed by John R. Garske Date 12/29/93  
Surveyor's Michigan License No. 28410